


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
NICHOLS POND DAM (VT.) (U) CORPS OF ENGINEERS WALTHAM MA
NEW ENGLAND DIV APR 80

1/2

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

PHOTOGRAPH THIS SHEET

AD-A156 255

DTIC ACCESSION NUMBER

11

LEVEL

1

INVENTORY

Nichols Pond Dam VT00184

DOCUMENT IDENTIFICATION

APR 1980

This document has been approved
for public release and its
distribution is unlimited.

DISTRIBUTION STATEMENT

ACCESSION FOR

NTIS GRA&I ☒

DTIC TAB ☐

UNANNOUNCED ☐

JUSTIFICATION

BY

DISTRIBUTION /

AVAILABILITY CODES

DIST

AVAIL AND/OR SPECIAL

A-1

DISTRIBUTION STAMP

DTIC
JUL 03 1985
S E D

DATE ACCESSIONED

DATE RETURNED

85 7 08 087

DATE RECEIVED IN DTIC

REGISTERED OR CERTIFIED NO.

PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-DDAC

AD-A156 255

RICHELIEU RIVER BASIN
WOODBURY, VT

NICHOLS POND DAM
VT 00184

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

APRIL 1980

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER VT 00184	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Nochols Pond Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
12. REPORT DATE April 1980		13. NUMBER OF PAGES 47
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Richelieu River Basin Woodbury VT. Nochols Brook		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is a 200 ft. long, 18 ft. high earth and masonry structure. The visual inspection of the dam revealed some minor problems. The general condition of the dam is considered fair. The dam is intermedaite in size with a high hazard potential. There are a few recommendations which must be undertaken by the owner.		

NATIONAL DAM INSPECTION PROGRAM
PHASE I - INSPECTION REPORT
BRIEF ASSESSMENT


Identification Number: 00184
Name of Dam: Nichols Pond Dam
Town: Woodbury
County and State: Washington, Vermont
Stream: Nichols Brook
Date of Inspection: October 25, 1979

Nichols Pond Dam is a 200-foot-long, 18-foot-high earth and masonry structure. The dam was originally constructed in about 1900 to provide water supply for the generation of hydroelectric power at Mackville Dam, 2½ miles downstream. Water from Nichols Pond currently augments flows at Pottersville Dam on the Lamoille River. There is a concrete chute spillway approximately in the center of the earth structure which controls normal outflow. There is no emergency spillway and the service spillway is only 7' - 3" wide at its downstream end. Reportedly, a rectangular sluice (2 ft by 5 ft) controlled by two hand operated gates is located underneath the service spillway. The only engineering information available on the structure consisted of past inspection reports by two bureaus of the State of Vermont. There are no design calculations or construction data available.

The visual inspection of Nichols Pond Dam revealed some minor problems. The general condition of the dam is considered fair. The inspection revealed erosion on the crest of the dam, a large mass of debris that deflected flows toward the base of the downstream face, trees growing on the crest and overhanging the downstream channel, deterioration of the gate operating mechanism, no emergency spillway and trespassing on the crest. Based on the dam's Intermediate size and High hazard classification in accordance with the Corps' guidelines, the test flood is the full PMF. The test flood for a drainage area of 4.6 square miles is approximately 8,300 cfs. Storage provided by the pond (1,335 acre-feet) will attenuate the test flood to a projected outflow of 5,870 cfs which will overtop the dam by 5.0 feet. The spillway will discharge 218 cfs (3.7% of the routed test flood outflow) with a water level at the top of the dam.

It is recommended that the owner engage a qualified registered engineer to design appropriate structures to control erosion at the base of the spillway and control the accumulation of debris, examine both upstream and downstream faces where not presently visible, perform a hydraulic analysis of the spillway, design an emergency spillway, evaluate the gate structure, and initiate an active maintenance program. The owner should develop a formal surveillance and downstream flood warning plan, including round-the-clock monitoring during heavy precipitation.

The recommendations and remedial measures are described in Section 7 and should be addressed within one year after receipt of this Phase I Inspection Report by the owner.



JJB/tdc

Very truly yours,

DuBois & King, Inc.

John J. Bilotta
John J. Bilotta, P.E.
Project Manager

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably-possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that

a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Letter of Transmittal	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	iii-v
Overview Photo	
Location Map	

REPORT

1. PROJECT INFORMATION	1
1.1 General	1
a. Authority	1
b. Purpose of Inspection	1
1.2 Description of Project	1
a. Location	1
b. Description of Dam and Appurtenances	1
c. Size Classification	2
d. Hazard Classification	2
e. Ownership	2
f. Operator	2
g. Purpose of Dam	2
h. Design and Construction History	3
i. Normal Operational Procedure	3
1.3 Pertinent Data	3
a. Drainage Area	3
b. Discharge at Dam Site	3
c. Elevation	4
d. Reservoir	4
e. Storage	4
f. Reservoir Surface	5
g. Dam	5
h. Diversion and Regulatory Tunnel	5
i. Spillway	5
j. Regulating Outlets	5

<u>Section</u>	<u>Page</u>
2. ENGINEERING DATA	6
2.1 Design Data	6
2.2 Construction Data	6
2.3 Operation Data	6
2.4 Evaluation of Data	6
a. Availability	6
b. Adequacy	6
c. Validity	6
3. VISUAL INSPECTION	7
3.1 Findings	7
a. General	7
b. Dam	7
c. Appurtenant Structures	8
d. Reservoir Area	8
e. Downstream Channel	8
3.2 Evaluation	9
4. OPERATIONAL AND MAINTENANCE PROCEDURES	10
4.1 Operational Procedure	10
a. General	10
b. Description of any Warning System in Effect	10
4.2 Maintenance Procedures	10
a. General	10
b. Operating Facilities	10
4.3 Evaluation	10
5. EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES	11
5.1 General	11
5.2 Design Data	11
5.3 Experience Data	12
5.4 Test Flood Analysis	12
5.5 Dam Failure Analysis	12

<u>Section</u>	<u>Page</u>
6. EVALUATION OF STRUCTURAL STABILITY	13
6.1 Visual Observation	13
6.2 Design and Construction Data	13
6.3 Post-Construction Changes	13
6.4 Seismic Stability	13
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	14
7.1 Dam Assessment	14
a. Condition	14
b. Adequacy of Information	14
c. Urgency	14
7.2 Recommendations	14
7.3 Remedial Measures	15
a. Operation and Maintenance Procedures	15
7.4 Alternatives	15

APPENDICES

APPENDIX A - INSPECTION CHECKLIST

APPENDIX B - ENGINEERING DATA

APPENDIX C - PHOTOGRAPHS

APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS

APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL
INVENTORY OF DAMS



OVERVIEW PHOTOGRAPHS-NICHOLS POND DAM

SECTION 6 EVALUATION OF STRUCTURAL STABILITY

6.1 Visual Observations

The visual observations did not disclose any indications of present structural instability. Undermining of the downstream wall next to the spillway, if worsened, could endanger the future stability of the dam. The debris at the spillway outfall prevented the gathering of data for an analysis of the sluice structure.

6.2 Design and Construction Data

There is practically no design and construction data available. Thus it is not possible to perform a formal analysis of the stability of the dam. A report of an inspection performed by the Public Service Commission in 1949 provides some details but the data is insufficient to perform any analysis.

6.3 Post Construction Changes

There are no post construction changes noted in the available records except for the repairs to the concrete of the upstream concrete face and spillway. The repaired concrete was observed to be in good condition.

6.4 Seismic Stability

The dam is located in Seismic Zone 2 and in accordance with the Phase I inspection guidelines does not warrant seismic analysis.

5.3 Experience Data

There are no recorded experiences of overtopping or any visual accounts of such. However, the rather limited capacity of the spillway (218 cubic feet per second) would tend to indicate that overtopping would occur on frequent basis. The scour or erosion noted on the top of the dam adjacent to the spillway may be an indication of overtopping.

5.4 Test Flood Analysis

of dam.

The storage capacity of this structure (2840 acre-feet) puts it in the Intermediate size category. The hazard classification is High, since failure of Nichols Pond is likely to endanger the lives of more than a few people at Mackville and result in subsequent overtopping of Mackville Dam (two miles downstream). A failure of Nichols Pond Dam would likely endanger occupants of five dwellings located near Mackville Pond. Based upon "Recommended Guidelines for Safety Inspection of Dams" the test flood is the full Probable Maximum Flood (PMF). The drainage area for Nichols Dam consists of a regulated drainage area (3.4 square miles is controlled by East Long Pond Dam) and an independent drainage area (1.1 square miles). The PMF inflow to Nichols was obtained by adding the routed test flood outflow from East Long Pond Dam to the inflow projected from the independent drainage area. The PMF envelope curve for Mountainous Areas was used to project inflows for the two drainage areas. The resulting test flood inflow (8300 cfs) for Nichols dam was then routed through the reservoir assuming the water surface to be initially at the crest of the dam (elevation 1130.5 NGVD). Calculations indicate that the dam would be overtopped by 5.0 feet (elevation 1135.5 NGVD). The resulting storage (1335 acre-feet) would attenuate the inflow to 5870 cfs outflow. ~~The routed test flood outflow (5870 cfs) represents a 29% reduction of the test flood inflow.~~

1/2 PMF analysis is also required for high hazard dam. Summary.

previously commented → Give spillway capacity at top of dam and percentage of routed test flood outflow spillway can carry at top of dam.

5.5 Dam Failure Analysis

Utilizing the Corps' April, 1978, "Rule of Thumb Guidance for Estimating Downstream Dam Failure Hydrographs," a dam failure analysis was performed for Nichols Pond. Prior to failure, the water level was assumed to be at the crest of the dam (1130.5 NGVD) and the breach height (upstream toe to water surface) would be 20 feet. A breach width of 70 feet was used in the Saint-Venant equation to compute a breach outflow of 10,500 cfs.

The breach would produce a 11.9-foot high flood wave and the resultant stage of Nichols Brook would be 13.7 feet above streambed at the initial impact area. Approximately two miles downstream lies Mackville Dam. The flood wave would cause subsequent overtopping of Mackville Dam. Appreciable damage could occur to five dwellings located at Mackville with flood levels up to five feet above the first floor of some of those dwellings. Another residential area one-half mile further downstream than Mackville has about ten more residences that would be subject to damages resulting by an 11.6-foot high flood wave. Further downstream the outskirts of Hardwick Village would be subjected to a flood wave 6.8 foot high. It is likely that more than a few lives may be lost if Nichols dam is breached, and therefore the dam is classified as High hazard.

SECTION 5 EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

5.1 General

Nichols Pond has a fixed crest weir for a principal spillway 37.0 feet wide set at elevation 1128.0. There is a 9 feet wide notch in the crest approximately 6-inches deep. The notch tapers to the width of 7 feet 3-inches and an elevation of 1126.0 at the downstream face. The only outlet for water at the downstream face of the spillway is a notch 7 feet 3 inches wide and 4 feet high. For various flows in the small range, the control for the pool level varies from the upstream to the downstream end. For flows less than 100 cfs, the upstream end of the spillway represents the control. For flows greater than 100 to 150 cfs, the downstream 4 feet deep notch represents the control of the spillway. It is suspected that when flow over the spillway is in a range of 75 to 150 cfs a hydraulic jump may occur in the middle of the spillway. Evidence of this phenomenon is represented by a scour mark approximately three-quarters of the way down the notch in the spillway.

The pond outlet is controlled by two gates with wooden stems which rise vertically in the center of the spillway in the upstream face. There is no information available on the size or invert of the outlet structure. Consequently, no rating or other analysis was performed for the outlet. The location of the gate operating mechanism in the center of the spillway would obviously prevent gate operation during periods of high water.

The watershed of Nichols Pond is relatively steep mountainous terrain covered for the most part with trees and forests. Approximately one-half mile upstream from Nichols Pond lies another large (for this watershed) lake named East Long Pond. The combination of East Long Pond and Nichols Pond have a total lake area at full pool of 350 acres. This represents 12 percent of the total watershed. It is likely that this large lake area will attenuate flood peaks. Both East Long Pond and Nichols Pond are owned and operated by the Village of Hardwick.

5.2 Design Data

The data on the hydrologic design of Nichols Pond Dam is not available. However, a preliminary analysis of the hydraulic characteristics of the spillway indicate that hydraulic control may switch from the upstream face to the throat of the spillway. This may result in a hydraulic jump occurring in the middle of the spillway.

SECTION 4
OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 Operational Procedures

a. General. Operational Procedures consists primarily of opening the gates in the summer time in order to augment flows to the power dam downstream on the Lamoille River. In order to operate the sluice gates, the operator must stand on the crest of the spillway and use a large wrench to turn the ratchet which raises and lowers the timbers attached to the gates. The wrench is kept at the Village maintenance shed approximately three miles downstream. There is no written procedure for lowering the pool level or opening the gates in preparation for a possible flooding event. A 1949 inspection report by an engineer for the Public Service Commission warned that both East Long Pond and Nichols Pond should not be kept full during flood season. The "flood season" was not defined. There is neither any indication that the policy was adopted nor any written operational tool for establishing the level of the two ponds.

b. Warning System. There is no system either to warn of an impending flood or to warn of possible overtopping.

4.2 Maintenance Procedures

a. General. There is no set program for maintaining the dam. Maintenance is performed on an "as-needed" basis. The only operating facilities on the dam are the two sluice gates. At the time of the inspection, the timber stems for both gates were deteriorated and showed signs of rot. There is no established procedure for maintaining these facilities.

4.3 Evaluation

There is a possibility of a serious problem at the downstream end of the spillway. Just beyond the vertical face there is an enormous mat of trees, branches, general trash, and other debris which has accumulated downstream of the spillway. Spillway flows impinge upon this debris and are scattered sideways, possibly causing an undermining of the downstream foundation. There is no written procedure for clearing the debris from the base of the spillway although it was reportedly a regular problem. The general operational and maintenance procedures can be described as poor. The rotten gate stems, the debris at the base of the spillway and the trees growing on the downstream area are indications of neglect.

Current procedures are considered to be inadequate to insure that all problems encountered can be remedied within a reasonable period of time. The owner should establish written procedures for operating and maintaining the structure.

3.2 Evaluation

On the basis of the visual inspection, the dam is judged to be in fair condition. The following features if left unattended could result in the deterioration of the dam:

- a. Erosion of soil and resulting undermining of the downstream walls next to the spillways can endanger the stability of the walls. The erosion is probably worsened by the debris accumulated downstream of the spillway which in part deflects the flow laterally.
- b. A cavity produced by erosion of earth fill against the left spillway wall, if enlarged, can result in damage to the spillway floor and left wall which in turn could cause flow into the cavity and further erosion. Enlarging of the cavity will develop rapidly in case of overtopping of the dam.
- c. The roots of trees growing at the crest next to the downstream wall can exert pressures against the downstream wall.
- d. The condition of the downstream spillway wall and its foundation requires inspection after removal of the debris at the spillway discharge.
- e. The scour or spalling of the spillway walls may indicate a serious problem with the original design of the spillway. The unusual throat configuration at the downstream end of the spillway may become the hydraulic control, thereby forcing a hydraulic jump in the middle of the spillway. The resulting roller could be the origination of the scour to the left of the spillway as shown in photo 6.

These walls do not reach the elevation of the crest (photo 7). The stone wall appears in good condition and no evidence of seepage was observed in the wall. There are indications of minor lateral movement of the stone wall at mid-height. The concrete walls are also in good condition except for undermining that has occurred at the base of the concrete wall left of the spillway creating a void about 2 feet long and $\frac{1}{2}$ inch deep. The concrete walls appear slightly bowed at mid-height. A seam observed at mid-height in the left concrete wall (Photo 8) may be the result of movement of concrete forms during initial construction. A masonry patch has been applied to the seam on the downstream face of the wall. Some efflorescence was also observed on the downstream face (Photo 9). There is some trespassing right of the spillway which has caused some deterioration of the downstream wall. The right bank downstream of the dam has an accumulation of debris. (photo 10).

There is a wet area about 20 ft. downstream of the dam, left of the spillway (photo 1). No water flow was evident.

c. Appurtenant Structures The spillway walls and floor appear in good condition (photo 11) with some apparent spalling of the floor near the downstream end, (photo 12) Minor cracks in the spillway walls are typical of the cracks caused by concrete shrinkage (photo 13). The downstream face of the spillway could not be observed due to a large amount of debris accumulated against it (photo 14). An undesirable effect of the accumulated debris is a lateral deflection of the water flow resulting in erosion of the banks of the downstream channel adjacent to the dam. The erosion is evident on the left back of the downstream channel (photo 14) where the stump of a tree has rotated about 90°. This erosion could be responsible for the undermining of the concrete wall, as discussed in the previous section. Due to the debris accumulation, it was not possible to observe the condition of the downstream wall of spillway and of the downstream channel bottom immediately downstream for evidences of scour (photo 15).

The gate mechanism for a low-level outlet (photo 16) is a pair of wooden vertical elements which have deteriorated and require replacement. The gate mechanism would not be accesible during floods. The outlet conduit could not be observed due to the debris at the downstream end.

d. Reservoir Area. There were no evidences of instability along the reservoir edge in the vicinity of the dam.

e. Downstream Channel. The downstream channel is the natural streambed. A small timber bridge for a logging road about 100 feet downstream of the dam would not present a significant obstruction to the flow. There is an abandoned dam, approximately 5 feet high, located about 100 yards downstream. The structure has been breached from the streambed to the right bank. Consequently it was not considered a significant obstruction to flow. There are a few overhanging trees along the downstream channel (Photo 15).

SECTION 3 VISUAL INSPECTION

3.1 Findings

a. General. The field inspection of Nichols Pond Dam was performed on October 25 and 26, 1979. The weather was cloudy and cold with temperatures near 32°F. The inspection team included personnel from DuBois & King, Inc.; Geotechnical Engineers Inc.; Knight Consulting Engineers, Inc.; and a representative of the Village of Hardwick. A copy of the inspection checklist as completed during the field inspection is included as Appendix A. At the time of the inspection, the water was at full pool and flowing over the spillway. Consequently, no assessment could be made of the upstream face of the structure.

b. Dam. The dam consists of an earthen embankment with a dry masonry downstream face (photo 1) and a concrete upstream face (photo 2). The upstream face of the dam is a vertical concrete wall (photo 3). A new wall has been built immediately upstream of the original wall. The exposed part of the new wall appears in good condition with only minor spalling and cracking, while the old wall shows severe spalling in its exposed upper part (photo 4). The old wall appears to have settled slightly, on the right side of the spillway. The new wall does not show evidence of settlement.

The crest of the dam is grass covered with the exception of an area near the right abutment which is used for parking. Near the left abutment and also along the downstream edge, there are trees growing on the crest (photo 2). The elevation of the crest is somewhat irregular with areas higher and lower than the elevation of the top of the spillway walls. Adjacent to the left spillway wall there is a cavity about 3 to 4 ft. deep (photo 6). Further downstream along the left spillway wall, there is another cavity against the downstream wall (photo 5). It is possible that the two cavities are connected and may have formed when the dam has been overtopped and water has flowed into the upstream cavity and then downwards between the downstream wall and earth fill.

The downstream face of the dam consist of a dry masonry stone wall (photo 1) and concrete walls next to the spillway.

SECTION 2 ENGINEERING DATA

2.1 Design

Information on the design as well as specifications were not available for Nichols Pond Dam. The field sketch for this dam shows observable dimensions only.

2.2 Construction Data

Reports and records of construction were not available.

2.3 Operation

No operating manual was available for Nichols Pond Dam. Operating personnel reported that the facilities were operated annually to effect flow augmentation for hydro-power. There is no known schedule for monitoring the structure. There are records of past inspections performed by the Vermont Department of Water Resources and the Public Service Commission. These reports were valuable since they supplied additional dimensions which were unavailable at the time of the visual inspection.

2.4 Evaluation

a. Availability. The available information is not sufficient for stability analyses of the dam or the appurtenant structures. The only background data which could be located consisted of inspection reports by the Public Service Board and the Department of Water Resources of the state of Vermont.

b. Adequacy. The lack of engineering data did not allow for a definitive review. Therefore, the adequacy of this dam could not be assessed from the standpoint of reviewing design and construction data. All assessments were based primarily on the visual inspection, records of past performance, and sound hydrologic and structural engineering judgment.

c. Validity. Not applicable.

f. Reservoir Surface (acres).

1. Normal Pool	162
2. Flood-Control Pool	N/A
3. Spillway Crest	162
4. Test Flood Pool	182
5. Top of Dam	167

g. Dam

1. Type	earth and masonry structure
2. Length	approximately 200 feet
3. Height	approximately 18 feet
4. Top Width	30 feet (varies)
5. Side Slopes	Vertical
6. Zoning	N/A
7. Impervious Core	N/A
8. Cut-Off	Unknown
9. Grout Curtain	Unknown
10. Other	N/A

h. Diverson and Regulating Tunnel. Not Applicable.

i. Spillway.

1. Type	Concrete overflow in center of dam
2. Length of Weir	Varies from 37 feet to 7.25 feet
3. Crest Elevation	Varies from 1127.5 to 1126.0
4. Gates	N/A
5. Upstream Channel	N/A
6. Downstream Channel	Natural river bed

j. Regulating Outlets. Two sluice gates are located in the center of the dam. Reportedly, the outlet conduit is a 2 ft by 5 ft rectangular sluice. The gates are hand operated through a ratchet mechanism located in center of the principal spillway.

(4) Spillway Capacity at Test Flood Elevation. The capacity of the spillway at test flood (elevation 1135.5 NGVD) is approximately 600 cfs. This represents approximately 10% of the routed test flood outflow.

(5) Total Project Discharge at Top of Dam. At the top of the dam, the project will discharge 218 cfs at elevation 1130.5.

(6) Total Project Discharge for Test Flood Elevation. The total project will discharge 5,870 cfs at 1135.5 elevation.

c. Elevation (NGVD)

1. Stream Bed at Toe of Dam	1110 ±
2. Bottom of Cut-off	Unknown
3. Maximum Tailwater	Unknown
4. Recreation Pool	1127.5
5. Full Flood Control Pool	N/A
6. Spillway Crest (Ungated)	1127.5
7. Design Surge (Original Design)	Unknown
8. Top of Dam	1130.5
9. Test Flood Design Surge	1135.5

d. Reservoir (length in feet). Nichols Pond is approximately circular in plan, and it is 3,700 feet from the dam to the inflowing stream at normal pool. At the test flood elevation (1135.5) the pond would be about 5,000 feet long.

e. Storage (acre-feet).

1. Normal Pool	2590
2. Flood Control Pool	N/A
3. Spillway Crest Pool	2590
4. Top of Dam	2841
5. Test Flood Pool	3925

h. Design and Construction History. The history of the design and construction of Nichols Pond Dam is not available. It was reportedly constructed circa 1900.

i. Normal Operating Procedure. Nichols Pond Dam is maintained for flow augmentation for a power dam on the Lamoille River. The gates are reportedly opened in mid-summer and the pond level is maintained at approximately the spillway level (1127.5 NGVD). The gates are then closed in the spring to raise the pool level above the spillway level.

1.3 Pertinent Data

a. Drainage Area. The drainage basin of Nichols Pond Dam includes an area of 4.6 square miles. The land is mostly forested and the terrain is extremely steep and mountainous. One-half mile upstream along Nichols Brook, lies East Long Pond Dam which controls 3.5 square miles of the watershed. The basin is sparsely populated and there are very few houses and practically no paved roads.

The maximum reservoir area of 167 acres represents approximately 6% of the total drainage area. The predominant soils in the watershed are Glover-Calais and Calais-Buckland.

b. Discharge at the Dam Site.

(1) Outlet Works. Two sluice gates are located in the center of the structure. The gate operating mechanism consists of a timber riser attached to a ratchet system which is operated by a large wrench. In order to operate the gate mechanism, the operator has to stand in the center of the spillway. Consequently, the gates could not be operated during flood flows. Reportedly, the outlet conduit is a 2 ft by 5 ft rectangular sluice located in the center of the dam. The inlet of the sluice is located approximately 13.5 feet below the top of the dam.

(2) Maximum Known Flood. There were no records available nor were there any witnesses of any past flooding at the site.

(3) Spillway Capacity at Top of Dam. The principal spillway is a 37-foot wide structure which is notched approximately in the center. At the upstream end of the spillway, the notch is six inches deep and nine feet wide. At the downstream end of the spillway, the notch is four feet deep and 7 foot 3 inches wide. Above 100 cfs it is considered that this downstream throat would provide control by critical depth. This is the only uncontrolled outflow for the structure and its capacity at the top of the dam elevation 1130.5 is approximately 218 cfs (3.7% of the routed test flood outflow).

The upstream face has been capped with two layers of concrete. The downstream face is a dry-stone masonry wall in some places and there has been concrete facing applied to a certain area in the center of this structure. The dam itself is bisected by a concrete spillway which varies in width from 37 feet at the upstream end to 7 feet 3 inches at the downstream end. The spillway varies in depth from 1.5 feet at the upstream end to 4 feet at the downstream end. The crest of the dam varies in elevation between 1130 feet above mean sea level to 1131 feet above mean sea level. The lowest point in the spillway is at elevation 1127.5. The inlet invert of the sluice is approximately at elevation 1117.0 NGVD.

There is neither any emergency spillway nor any other provision for discharging flood flows.

c. Size Classification. Nichols Pond Dam is 18 feet high and has a storage capacity of 2840 acre-feet. In accordance with article 2.1.1 of the Recommended Guidelines for Safety Inspection of Dams, the dam is Intermediate in size based upon its storage capacity which is greater than 1000 acre-feet and less than 50,000 acre-feet.

d. Hazard Classification. The dam has a hazard classification of High based upon its potential for damage. Approximately 2 miles downstream lies Mackville Dam. The flood wave generated by a breach of Nichols Pond Dam with a water level at the top of the dam would be approximately 11.4 feet high when it reached the Mackville Dam Pond. It is considered that the flood wave generated by a breach of Nichols Pond Dam would cause subsequent overtopping of Mackville Dam. Appreciable damage could occur to five dwellings located at Mackville with flood levels up to five feet above the first floor of some of those dwellings. Another residential area one-half mile further downstream than Mackville has about ten more residences that would be subject to the resultant flood by an 11.6-foot-high wave. The outskirts of the Village of Hardwick would be subjected to a flood wave 6.8 feet high. It is possible that more than a few lives may be lost if Nichols Pond Dam is breached.

e. Ownership. This dam is owned by the Village of Hardwick Electric Light Department. The dam was originally owned by Woodbury Granite Company and then by Green Mountain Power Corporation before it was acquired by its present owner.

f. Operator. The dam is operated and maintained by the Village of Hardwick, Vermont 05843. Mr. William Fee, Village Manager, is in charge of all Village equipment. His telephone number is 802/472-5201.

g. Purpose. The original purpose of the dam was to provide water supply to operate Mackville Dam for power generation. The power generating facilities of Mackville Dam have been eliminated; however, the outflow from Nichols Pond Dam is used to augment the flows for another dam on the Lamoille River at Pottersville which generates power for the Village of Hardwick Electric Light Department.

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT
NICHOLS POND DAM

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. DuBois & King, Inc., has been retained by the New England Division to inspect and report on selected dams in the State of Vermont. Authorization and notice to proceed were issued to DuBois & King, Inc., under a letter of October 19, 1979 from William E. Hodgson, Jr., Colonel, Corps of Engineers. Contract No. DACW33-80-C-0003 has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.


(2) To encourage and prepare the states to quickly initiate effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. Nichols Pond Dam is located in the Town of Woodbury, Vermont on Nichols Brook approximately three miles upstream from its confluence with Cooper Brook. The dam is shown on the 15 minute U.S.G.S. Quadrangle for Plainfield, Vermont, with coordinates approximately 72° 20.6' west longitude, 44° 27.7' north latitude, Washington County, Vermont. The location of Nichols Dam is shown on the location map immediately preceding this page.

b. Description of Dam and Appurtenances. Nichols Pond Dam is an earth and masonry structure approximately 18 feet high with vertical walls both upstream and downstream. The breadth of the structure varies from 28 to 44 feet with an average breadth of approximately 30 feet.



DuBois & King
INC.

engineering and environmental services
PLAINFIELD VERMONT 05759 NEW HARTFORD CT

NATIONAL DAM INSPECTION PROGRAM

NICHOLS POND DAM

LOCATION MAP

USGS QUAD - PLAINFIELD, VERMONT

DRAWN BY JAS DATE 12/79

CHECKED BY RMC PROJ NO. 91118

PROJ ENG DRAW NO

SCALE: 1" = 62500'

SECTION 7
ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual inspection indicated the dam to be generally in fair condition. Items that could result in deterioration of this condition are:

- Erosion of soil downstream of dam, next to spillway, and resulting undermining of the downstream wall of the dam.
- A cavity at the crest, next to the left spillway wall.
- Trees growing next to the downstream wall.
- The timber risers that serve as gate stems are badly deteriorated.
- No emergency spillway.
- Scouring and spalling of the spillway.

The assessment of the present condition of the dam is subject to verification by inspection of the downstream wall of the spillway which could not be observed due to accumulation of debris.

b. Adequacy of Information. The information available was practically nil and thus the assessment of the condition of the dam is based solely on the visual inspection.

c. Urgency. The recommendations presented in Section 7.2 and 7.3 should be carried out within one year of receipt of this report by the owner.

7.2 Recommendations

The following investigations and needed corrections should be performed under the direction of a registered engineer qualified in the design and construction of dams.

Removal of debris that has accumulated downstream of the spillway and examination of the downstream spillway wall and its foundation for scour and possible undermining, and design of any repairs which might be needed.

Design measures to prevent accumulation of debris at the spillway discharge. This may include the design and installation of a log boom across the intake channel.

Design an appurtenant structure for the base of the spillway to prevent erosion of banks immediately downstream of the spillway. This may include an additional structure such as a "plunge pool" or a re-regulating weir to provide backwater.

Hydraulic analysis of the spillway to determine whether or not a hydraulic jump will form within the confines of the spillway. This may precipitate the redesign of the spillway structure to eliminate this undesirable occurrence.

Hydrologic and economic evaluation of the installation of an emergency spillway of sufficient capacity to protect the safety of the dam. This may include the raising of the structure to safely pass a design flood.

Replacement of deteriorated timber stems and a thorough examination of the gates and trash rack.

7.3 Remedial Measures

a. Operation and Maintenance Procedures

1. Remove trees and bushes growing on the crest and overhanging the downstream channel.
2. Fill the cavity next to the spillway left wall with lean concrete or compacted clayey soil.
3. Repair cracked and spalled concrete on the principal spillway.
4. Restrict trespassing from the crest of the structure.
5. Establish a program of annual technical inspections by a registered qualified engineer.
6. Develop a formal surveillance and downstream flood warning plan including round-the-clock monitoring during heavy precipitation.

7.4 Alternatives

There are no alternatives which are consistent with the present uses of the dam.

APPENDIX A
VISUAL CHECKLIST WITH COMMENTS

INSPECTION CHECK LIST

PARTY ORGANIZATION

PROJECT NICHOLS POND

DATE 10-25-79

TIME P.M.

WEATHER COOL

W.S. ELEV. _____ U.S. _____ DN.S

PARTY:

- | | |
|---|-----------|
| 1. <u>John Bilotta D&K</u> | 6. _____ |
| 2. <u>Jeffrey Spaulding D&K</u> | 7. _____ |
| 3. <u>Gonzalo Castro GEI</u> | 8. _____ |
| 4. <u>Stephen Knight KCE</u> | 9. _____ |
| 5. <u>Erwin Gileris Village of Hardwick</u> | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Structure</u>	<u>S. Knight</u>	
2. <u>Foundations</u>	<u>G. Castro</u>	
3. <u>Hydraulics/Electric Mechanical</u>	<u>J. Bilotta</u>	
4. _____		
5. _____		
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		

INSPECTION CHECK LIST

PROJECT NICHOLS POND DAM

DATE 10-25/26-79

PROJECT FEATURE _____

NAME J. Bilotta

DISCIPLINE _____

NAME S. Knight KCE

NAME G. Castro GEI

AREA EVALUATED	CONDITIONS
<u>DAM ENBANKMENT</u>	
Crest Elevation	Earth with upstream vertical concrete face and downstream vertical stone face.
Current Pool Elevation	1-inch over spillway crest.
Maximum Impoundment to Date	Unknown
Surface Cracks	A few cracks on upstream face.
Pavement Condition	N.A.
Movement or Settlement of Crest	Possible settlement of old upstream concrete face to right of spillway.
Lateral Movement	None observed.
Vertical Alignment	Crest very irregular.
Horizontal Alignment	Downstream stone wall bowed Downstream concrete bowed-likely due to defective form.
Condition at Abutment	Minor erosion at end of concrete wall at right abutment(u.s.)
Indications of Movement of Structural Items on Slopes	N.A.
Trespassing on Slopes	Downstream edge of crest right of spillway - footpath. Also logging road around right end which is at same elevation as dam.
Vegetation on Slopes	Some at earth slope near right abutment.
Sloughing or Erosion of Slopes or Abutments	Erosion of crest against left wall of spillway.
Rock Slope Protection - Riprap Failures	N.A.

INSPECTION CHECK LIST

PROJECT NICHOLS POND DAM

DATE 10-25/26-79

PROJECT FEATURE _____

NAME J. Bilotta D&K

DISCIPLINE _____

NAME S. Knight KCE

NAME G. Castro GEI

AREA EVALUATED	CONDITIONS
<p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. Approach Channel</p> <p>Slope Conditions</p> <p>Bottom Conditions</p> <p>Rock Slides or Falls</p> <p>Log Boom</p> <p>Debris</p> <p>Condition of Concrete Lining</p> <p>Drains or Weep Holes</p> <p>b. Intake Structure</p> <p>Condition of Concrete</p> <p>Stop Logs and Slots</p>	<p>None observable.</p> <p>Riser stems - vertical timbers that are used to raise gates are deteriorated.</p>

INSPECTION CHECK LIST

PROJECT NICHOLS POND DAM

DATE 10-25/26-79

PROJECT FEATURE _____

NAME J. Bilotta D&K

DISCIPLINE _____

NAME S. Knight KCE

NAME G. Castro GEI

AREA EVALUATED	CONDITIONS
<u>OUTLET WORKS - CONTROL TOWER</u>	
A. Concrete and Structural	None as such.
General Condition	
Condition of Joints	
Spalling	
Visible Reinforcing	
Rusting or Staining of Concrete	
Any Seepage or Leaks in Gate Chamber	
Cracks	
Rusting or Corrosion of Steel	
b. Mechanical and Electrical	
Air Vents	None.
Float Wells	None.
Crane Hoist	None.
Elevator	None.
Hydraulic System	None.
Service Gates	Hand operated by a large wrench - we were told that it is operated at least annually not accessible when water flowing over spillway, wrench is kept at garage.
Emergency Gates	None.
Lighting Protection System	None.
Emergency Power System	None.
Wiring and Lighting System in Gate Chamber	None.

DAM EMBANKMENT CONTINUED

Unusual Movement or Cracking at or
near Toes

N.A. but there is a cavity
under concrete wall left of
spillway (0.5' x 2.0').

Embankment or Downstream Seepage

5' x 10' wet area 20' downstream
of dam opposite stonewall on
left of spillway.

Piping or Boils

None observed.

Foundation Drainage Features

None known.

Toe Drains

None known.

Instrumentation System

None known.

INSPECTION CHECK LIST

PROJECT NICHOLS POND DAM

DATE 10-25/26-79

PROJECT FEATURE _____

NAME J. Bilotta D&K

DISCIPLINE _____

NAME S. Knight KCE

NAME G. Castro GEI

AREA EVALUATED	CONDITIONS
<p><u>OUTLET WORKS - TRANSITION AND CONDUIT</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining on Concrete</p> <p>Spalling</p> <p>Erosion or Cavitation</p> <p>Cracking</p> <p>Alignment of Monoliths</p> <p>Alignment of Joints</p> <p>Numbering of Monoliths</p>	<p>Outlet of conduit not visible because of debris at discharge covering outlet completely.</p>

INSPECTION CHECK LIST

PROJECT NICHOLS POND DAM

DATE 10-25/26-79

PROJECT FEATURE _____

NAME J. Bilotta D&K

DISCIPLINE _____

NAME S. Knight KCE

NAME G. Castro GEI

AREA EVALUATED

CONDITIONS

OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL

General Condition of Concrete

Rust or Staining

Spalling

Erosion or Cavitation

Visible Reinforcing

Any Seepage or Efflorescence

Condition at Joints

Drain holes

Channel

Loose Rock or Trees
Overhanging Channel

Condition of Discharge
Channel

No outlet structure.

See spillway for condition
of channel.

INSPECTION CHECK LIST

PROJECT <u>NICHOLS POND DAM</u>	DATE <u>10-25/26-79</u>
PROJECT FEATURE _____	NAME <u>J. Bilotta D&K</u>
DISCIPLINE _____	NAME <u>S. Knight KCE</u>
	NAME <u>G. Castro GEI</u>

AREA EVALUATED

CONDITIONS

OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS

- | | |
|--------------------------------|--|
| a. Approach Channel | Non visible. |
| General Condition | N.A. |
| Loose Rock Overhanging Channel | N.A. |
| Trees Overhanging Channel | N.A. |
| Floor of Approach Channel | N.A. |
| b. Weir and Traing Walls | |
| General Condition of Concrete | Good. |
| Rust or Staining | Minor staining. |
| Spalling | Concrete spall in bottom of spillway channel apparently due to cavitation. |
| Any Visible Reinforcing | None observed. |
| Any Seepage or Efflorescence | None observed. |
| Drain Holes | None observed. |
| c. Discharge Channel | |
| General Condition | Full of debris for 30' downstream of dam |
| Loose Rock Overhanging Channel | None. |
| Trees Overhanging Channel | Yes, Several - some have fallen into channel. |
| Floor of Channel | Boulders |
| Other Obstructions | Logging road bridge at about 100' downstream |

NOTE: Both banks of discharge channel severely eroded adjacent to dam.

INSPECTION CHECK LIST

PROJECT NICHOLS POND DAM

DATE 10-25/26-79

PROJECT FEATURE _____

NAME J. Bilotta D&K

DISCIPLINE _____

NAME S. Knight KCE

NAME G. Castro GEI

AREA EVALUATED

CONDITIONS

OUTLET WORKS - SERVICE BRIDGE

No service bridge.

a. Super Structure

Bearings

Anchor Bolts

Bridge Seat

Longitudinal Members

Under Side of Deck

Secondary Bracing

Deck

Drainage System

Railings

Expansion Joints

Paint

b. Abutment & Piers

General Condition of Concrete

Alignment of Abutment


Approach to Bridge

Condition of Seat & Backwall

APPENDIX B
ENGINEERING DATA

APPENDIX B


1. There are no known records of design, construction or maintenance.
2. A copy of an inspection performed by Stephen Haybrook for the Public Service Commission can be found on pages B-2 through B-5. The inspection was dated October 26, 1949. A copy of an analysis performed in 1954 by Louis M. Laushey for the Public Service Commission appears on pages B-6 through B-11. A copy of an inspection performed in 1979 by A. Peter Baraanco for the Department of Water Resources can be found on pages B-12 through B-14. A letter report by Mr. Barranco describes some of the history on page B-15.
3. Plans and sketches prepared by DuBois & King, Inc., appear on figure B-1, page B-16. Information shown on these plans and sketches is based upon information in past inspection reports and observations made during the visual inspection. Dimensions or materials indicated at the time of inspection were not verified. Elevations shown are based upon USGS datum.
4. There are no known records of subsurface investigations.



Handkerch. 6 rule & cloth

11-2-14 EV

: 278





STATE OF VERMONT

AGENCY OF ENVIRONMENTAL CONSERVATION

Department of Fish and Game
Department of Forests, Parks, and Recreation
Department of Water Resources
Environmental Board
Division of Environmental Engineering
Division of Environmental Protection
Natural Resources Conservation Council

Montpelier, Vermont 05602
Department of Water Resources

WATER QUALITY DIVISION

October 12, 1979

MEMORANDUM

To: File
From: A. Peter Barranco, Jr., P.E., Dam Safety Engineer
Subject: Nichols Pond Dam - Woodbury (252-1)

The writer inspected subject dam, obtained dimensions and photographs on July 12, 1979.

Overall the dam appears to be in good condition but in need of brush and tree removal on crest and downstream slopes and debris removal below spillway.

The only items of some concern are two areas where erosion has occurred. One is a cavity about 10' long, 2-3' wide and 3' deep adjacent to the left spillway wall. It could not be determined if this resulted from overtopping or from subsidence due to soil being removed internally. The downstream face was so packed with debris (logs and branches) that an examination of the downstream base of the wall was not possible. The other area is about 30' left of the spillway on the downstream side of the crest. Since there is only about 1.5' of freeboard at normal pool and a relatively small spillway that is subject to blockage by debris, overtopping of this dam would appear likely.

There may be some leakage and undermining below downstream wall, however, debris prevented a close examination. Concrete in spillway and walls in generally good condition. Water level was about 0.4' above crest of low flow notch, or about 1.5' below crest. Crest is somewhat irregular. Wood in gate stems may be nearing end of its useful life.

vl

DAM INSPECTION STATUS

Name Nichols Pond DWR No. 252-1
 Town Woodbury NDS No. VT00 184
 Owner Village of Hardwick (Electric Dept) Hazard Class 2 *
 Address Hardwick, Vt Size Category II
 Telephone 472-5201 (Capt. Village Elect. Dept) Inspect every N/R years **
 Type EF/SU Height 18' Storage 1200' Use P(S) Juris. PSB

INSPECTION RECORD

** Not required. PSB jurisdiction
 DWR inspects when in area on
 informed basis.
 Condition Summary

Inspection Date	Inspected By	Report Date	Owner Notified	Condition Summary
6-9-49	SHH (PSC)	10-26-49		Fair. Repairs/maint. needed. Inadequate spillway
5-9-53	SHH (PSC)	5-9-53		Fair-poor. Some deterioration since last inspection.
11-22-54	PSC + Consultant	11-26-54	12-1-54	Fair-poor. Repairs needed. Inadequate spillway at 4/
7-27-73	DHS (DWR)	7-27-73		Good. No storm damage. Maint. needed.
7-12-79	APB (DWR)	10-12-79		Good. Erosion on crest. Brush & trees. Debris.

POTENTIAL DOWNSTREAM HAZARDS

Description	Miles Downstream	Remarks
Marksville Pond Dam	2.5	Subject to overtopping by Nichols Pond & E. Long Rd.
Marksville Village	2.6-3.1	TH bridge, power houses, structures, trailers?
Route 14 (Hardwick)	3.1	Bridge

* Hazard Class 2 based on possible overtopping and failure of Marksville Pond Dam

INFORMATION AVAILABLE

Plans 6-9-49 Dimensions (field check) 7-12-49 Photos 1979

INFORMATION NEEDED NEXT INSPECTION

Dimensions (field check) Detailed Survey Photos ✓
 Other

can handle floods safely. The rate of 800 cubic feet per second discharged from East Long Pond will be reduced some by channel storage, and Nichols Dam might possibly have to discharge 600 cubic feet per second plus the estimated 200 to 320 cubic feet per second from its own watershed. The sum would be of the order of magnitude of ^{not} more than 1000 cubic feet per second--which it could not do safely with its estimated capacity of not more than one-half this amount.

Some of these figures were estimated simply to get an approximate answer. With more complete information on the nature of the one-half mile long connecting stream and the reservoir characteristics at East Long Pond, more detailed calculations could give a more exact answer. However, it seems clear that the outflow capacity at Nichols Dam is adequate as long as both reservoirs are not full at the same time; under these latter circumstances the Nichols outflow capacity (spillway and sluice) would be about fifty percent adequate to handle a major flood on both areas.

Recommendations.-

1. Repair head wall, spillway slab and wall, and earth embankment as described previously.
2. Definitely avoid having both reservoirs full at the same time during seasons when heavy runoffs can be expected.

Louis M. Laushey
Louis M. Laushey
Professional Engineer

Fanning, for New England streams (maximum flow)

$$Q = 200(1)^{\frac{5}{6}} \approx 200 \text{ cubic feet per second}$$

Rational Formula (2" rain per hour, 25% runoff)

$$Q = (0.25) (2) (640) = 320 \text{ cubic feet per sec.}$$

All of these empirical formulas show rates less than the estimated 485 cubic feet per second capacity available. Although there have been many instances of much higher runoff rates from a one square mile area, because the area is forested it is believed that the discharge capacity of Nichols Dam is sufficient if inflows from East Long Pond are small or non-existent during a heavy storm and "full" reservoir at Nichols Pond.

Condition "b" above.

When both reservoirs are in flood simultaneously the discharge capacity at Nichols Dam can be estimated as follows: add to the flow from the Nichols watershed the estimated inflow rate minus the effect of storage.

From the previous calculations of the flood rates, corrected for the new drainage area of 3 square miles, it is likely that a peak flow between 500 and 1000 cubic feet per second can enter the East Long Pond reservoir. Information is lacking on storage capacity, but it can be estimated that say 800 cubic feet per second could be discharged. Although complete information is lacking, it is known that the sluice capacity alone is about three times that at Nichols Dam, and assuming the spillway is of the same order of relative magnitude, it appears likely that East Long Pond

Sluice Capacity: - The approximate sluice capacity is

$$Q = (5 \times 2)(8.02) \sqrt{\frac{(12 - 1) + 5}{1 + 0.5 + \left\{ 0.02 \times \frac{40}{4 \left(\frac{10}{14} \right)} \right\}}}$$

$Q = 240$ cubic feet per second

Combined Capacity: - The combined capacity of sluice and spillway. (at a head above the crest of 1.5 feet) is $240 + 245 = 485$ cubic feet per second. This should be sufficient to handle the drainage from a severe storm on the one square mile watershed - assuming no inflow from the East Long Pond Dam.

Inflow from East Long Pond Dam: - The required discharge capacity of Nichols Dam will be computed for two conditions which depend on the method of operation of the reservoir and the extent of the storm.

(a) no inflow from East Long Pond Dam, but "full" reservoir in Nichols Dam during a storm on the Nichols Dam Watershed only.

(b) inflow from East Long Pond Dam assuming both reservoirs "full" and a storm over both watersheds. This is of course, the most serious possibility.

Required Capacity: -

Condition "a" above - Nichols Dam should have a combined spillway and sluice capacity within the following limits to handle safely runoff from it's own watershed only.

Kuichling (for frequent floods)

$$Q = \left[\frac{111,000}{1 + 370} + 20 \right] 1.0 = 138 \text{ cubic feet per second}$$

The Embankment: - The embankment is well-sodded and quite stable. The downstream face is in good condition; no leakage was observed, although the pond level was low and leakage might occur through the disintegrated wall during high water.

Minor repairs are needed on a small section of the right bank beyond the head wall to fill and stabilize this section which has eroded out. The damage is not serious, but should be rectified when the head wall is repaired.

The Spillway: - The 6-inch thick spillway slab and the spillway guide walls are cracked in several places, probably due to settlement of the slab on the earth fill under the slabs. The bituminous filler previously used to attempt repairs is not effective, and leakage might occur through the cracks into the earth fill under the slab. The rock face which retains the earth fill on the downstream side of the spillway is in good condition.

The spillway slab and guide walls should be patched with new concrete to prevent leakage into the earth fill under the spillway slab when the spillway is in operation.

The Spillway Capacity: - The maximum safe capacity of the spillway is estimated to be:

$$Q = 3.7 \times 36(1.5)^{3/2} = 245 \text{ cubic feet per second}$$

245 cubic feet per second

feet.

The non-overflow section of the Nichols Pond Dam is an earth embankment with these approximate dimensions: length, 160 feet, width 26 feet, and height 14 feet. A concrete head wall, 12 inches wide extends the length of the embankment on the upstream side. The spillway is nearly in the center of the embankment, being 36 feet long at the crest, and capable of a maximum safe head of 1.5 feet. A rectangular sluice, 5 feet x 2 feet, controlled by 2 hand operated gates, also passes water downstream along the longitudinal center-line of the spillway.

The Head Wall: - The 12-inch wide concrete head wall is badly spalled and disintegrated. A bituminous joint sealer applied years ago to seal the cracks in the wall is not now effective. It is expected that leakage would occur when the pond is high, although none was noticed during the inspection because the pond was several feet below the spillway crest, and most of the serious disintegration was at a higher elevation. The stability of the dam is not affected by the disintegrated wall as long as leakage does not occur.

The head wall should be resurfaced by chipping out all unsound sections and replacing with new concrete adequately tied into the sound portion of the existing wall. This would not be a major project because most of the disintegration is at a high elevation.

*1 - House, Northfield
Hardwick Village*

Winch Hill Road
Northfield, Vermont
November 26, 1954

NOV 30 3 41 PM '54

Mr. Oscar L. Shepard
Chairman, State of Vermont
Public Service Commission
Montpelier, Vermont


Subject: Nichols Pond Dam

Dear Mr. Shepard:


Nichols Pond Dam was inspected on November 22, 1954 in accordance with the policy of the Vermont Public Service Commission to periodically check on the safety of the dams in the state. The inspection party consisted of Mr. Silas C. Carpenter, Engineer for the Public Service Commission, Mr. Larrabee, Superintendent for the Village of Hardwick, and the writer.

The owner and operator of the Nichols Pond Dam is the Village of Hardwick, Vermont. The dam is located near Woodbury, Vermont which is downstream from the dam. East Long Pond Dam and Reservoir are approximately one-half mile upstream from the Nichols Pond Dam.

Nichols Pond Dam forms a lake of approximately 125 acres, with a storage of approximately 54 million cubic feet. The drainage area is about 1 square mile. The East Long Pond overflow also discharges into the Nichols Pond. The drainage area above East Long Pond is approximately 3 square miles; the pond has an approximate area of 250 acres and storage of 43 million cubic



Plan View



Section A-A

Sketch of

Nichols' Pond Dam

Drawn by SHH
6/9/49

Conclusions:

The writer concludes that this dam is in a satisfactory structural condition but lacks adequate spillway capacity. Keeping one or both ponds below spillway crest level provides a margin of safety against overtopping and probable destruction of the dam. If, at some future time, it becomes desirable to maintain a full pond level at both Nichols Pond and East Long Pond, then consideration should be given to enlarging the spillway capacity.

Stephen H. Haybrook
STEPHEN H. HAYBROOK
HYDRAULIC ENGINEER

Public Service Commission
Montpelier, Vermont
October 26, 1949

Report No. 79

through seepage. Although the wall appeared in a weakened condition, it was considered stable enough to retain the embankment.

On date of visit the pond level was drawn down to about 5 ft. below crest level. With this low water it was impossible to determine what seepage, if any, occurred through the dam.

The embankment was well consolidated and sufficiently contained between its outside walls. Its top was protected by a sod cover. Both sluice gates were in good working order. The outlet and overflow structures were in good condition.

From all appearances the dam was being provided with the usual maintenance.

Comments re Dam:

At this dam the spillway capacity is limited. With both Nichols Pond and East Long Pond full at a time of maximum flood inflow, the spillway could not handle, simultaneously, the runoff from its own drainage area and the overflow from East Long Pond.

According to the operator, both ponds are never full at the same time. Either one or the other is generally drawn down below crest-level. With this method of operation, the possibility of overtopping Nichols Pond dam is greatly reduced.

It will be noted that both ponds are located in an isolated, wooded section. Consequently, the possibility of flood damage is also reduced.

*W. H. : E. H. :
L. : P. :*

REPORT ON NICHOLS POND DAM

Supplementing the storage of East Long Pond is Nichols Pond about 1/2 mile further downstream and on the same brook in the town of Woodbury, Vermont. This storage is used according to the needs of the owner's hydro-electric plant in the course of the stream. It is owned and operated by the Village of Hardwick.

The dam at the outlet creates a pond having a surface area of about 125 acres and a useable volume estimated at 54 million cubic feet. Besides the discharge from East Long Pond it receives the drainage from a catchment area of 1 square mile.

Description of Dam:



In general, the dam consists of an earth-fill contained between a concrete wall on the upstream side and a dry stone masonry wall on the downstream side. It is about 200 ft. in total length, 26 ft. in width and 14 ft. in height. A sketch of the dam is appended herein.

Discharge past the dam is provided by a rectangular concrete sluiceway, 5 ft. by 2 ft., and controlled by two hand operated wooden gates. Overflow is accommodated by a concrete-paved spillway trough 1.5 ft. below the top of the dam and located through its middle.

Notes from Inspection of June 9, 1949:

The concrete head wall making up the upstream face of the dam showed a battered effect due to wave and ice action. A bituminous material has been applied to the cracks to control

3



could not
see d/s face
11' below top of wall

Notes based on

Survey / Inspection 7-12-79 APB

Hot, Clear
Hand held, C'rule & cloth tape



STATE OF VERMONT

AGENCY OF ENVIRONMENTAL CONSERVATION

Montpelier, Vermont 05602
Department of Water Resources

Department of Fish and Game
Department of Forests, Parks, and Recreation
Department of Water Resources
Environmental Board
Division of Environmental Engineering
Division of Environmental Protection
Natural Resources Conservation Council

WATER QUALITY DIVISION

October 16, 1979

MEMORANDUM

To: File *A. Peter Barranco, Jr.*
From: A. Peter Barranco, Jr., P.E., Dam Safety Engineer
Subject: Mackville Pond Dam - Hardwick (93-2)





On July 12, 1979 the writer inspected subject structure and obtained photographs and additional dimensions.


The dam is in fair-poor condition, particularly because of lack of maintenance and repairs. Brush and tree growth made access and inspection difficult, however, despite its rundown condition the dam appears to be stable. The concrete training wall on the right downstream channel wall is in good condition. Leakage was noted along part of downstream face, however, it is about what one would expect of a dam of this construction and condition. Spillways are somewhat irregular due to loss of concrete cap and type of construction. Mortar on left upstream face has deteriorated.

While at the site, the writer spoke with Mr. Carroll Rowell who has lived in the house at the right end of the dam since 1913. Mr. Rowell is familiar with the history of this dam and the ones on Nichols Pond and East Long Pond - all of which were built by the Woodbury Granite Company. Mackville Pond Dam was apparently built about 1900. During the 1927 flood, the dam and bridge were overtopped but held, however, the right side of the pond (apparently old ground) washed out and destroyed several homes. The washout left a very deep ravine next to Mr. Rowell's house but did not damage the house because the erosion on that side was halted by ledge. After the flood, the washed out area and road were filled, however, the fill would not hold and it was necessary to drive steel sheet piling from near the right abutment across the town road a distance of 200-300' to hold it. The houses destroyed in the flood were not rebuilt.


During the 1973 flood, according to high water marks pointed out by Mr. Rowell, the pond level rose to 3.5' above spillway crest which would mean that the "non-overflow" sections were overtopped by about a foot.

REPRODUCED AT GOVERNMENT EXPENSE






PLAN
SCALE 1"=20'



ELEVATION
SCALE 1"=20'

- LEGEND**
- ① DIRECTION OF PHOTOGRAPH
 - ② POINT ELEVATION



(SAM)

DuBois & King engineering and environmental services RANDOLPH VERMONT / CONCORD NEW HAMPSHIRE		Department of the Army New England Division Corps of Engineers Waltham, MA 02154	
NATIONAL DAM INSPECTION PROGRAM NICHOLS POND DAM WOODBURY, VERMONT PLAN AND ELEVATION VIEW			
DRAWN JAS	ENGR FMC	PROJ. MGR	SCALE: AS SHOWN
		DATE: DECEMBER, 18, 197	
PLATE B-1			

APPENDIX C

PHOTOGRAPHS

FOR LOCATION OF PHOTOS, SEE FIGURE B-1
LOCATED IN APPENDIX B



1. Downstream face of left side of dam




2. Upstream view of dam from left



3. Upstream view of dam from right abutment



4. Close-up of upstream concrete wall.



5. Base of wall, left side of dam



6. Cavity to the left of spillway



7. Wall to right of spillway




8. Wall to left of spillway



9. Left wall showing efflorescence




10. Right bank, downstream of dam



11. Spillway looking downstream



12. Spalled area of spillway



13. Condition of spillway walls



14. Downstream face of spillway



15. View of dam from downstream



16. Gate operating mechanism

APPENDIX D
HYDROLOGIC AND HYDRAULIC CALCULATIONS

Job No. 9/110 Sheet 14 of 44
 Project East Long Pond Date 4/10/80
 Subject Hydraulics By RMC Ch'k. by

Surcharge height₅ = surcharge height₄ = 5.34 ≈ 5.3' (el 1211.1)

Values will not change, no further iterations necessary

Since dam is overtopped, 1/2 PMF must be routed to determine spillway adequacy

$Q_{P1} = 4050 \text{ cfs}$ surcharge height₁ = 4.6' (el 1212.6')

$$STOR_1 = 4120 - 3251 = 869 \text{ a-f}$$

$$STOR_1 = \frac{869 \text{ a-f} \times 12'' / \text{ft}}{3.44 \text{ mi}^2 \times 640 \text{ acres} / \text{mi}^2} = 4.7366''$$

$$Q_{P2} = Q_{P1} \left(1 - \frac{STOR_1}{9.5''}\right) = 4050 \left(1 - \frac{4.7366}{9.5}\right) = 2031 \text{ cfs}$$

surcharge height₂ = 3.3' (el 1211.3')

$$STOR_2 = 3860 - 3251 = 609 \text{ a-f}$$

$$STOR_2 = \frac{609 \times 12}{3.44 \times 640} = 3.3174''$$

$$STOR_{ave} = \frac{(3.3174 + 4.7366)}{2} = 4.0280$$

$$Q_{P3} = 4050 \left(1 - \frac{4.0280}{9.5}\right) = 2333 \text{ cfs}$$

surcharge height₃ = 3.5' (el 1211.5)

$$STOR_3 = 3900 - 3251 = 649 \text{ a-f}$$

$$STOR_3 = \frac{649 \times 12}{3.44 \times 640} = 3.5374''$$

$$STOR_{ave} = \frac{(3.5374 + 4.0280)}{2} = 3.7827''$$

$$Q_{P4} = 4050 \left(1 - \frac{3.7827}{9.5}\right) = 2437 \text{ cfs}$$

surcharge height₄ = 3.65' (el 1211.65')

No. 91110 Sheet 13 of 44
 ect East Long Pond Dam Date 1/28/80
 ject Hydraulics / Hydrology By Rmc Ch'k. by

STEP 3 EFFECT OF SURCHARGE STORAGE ON PMF

$$Q_{P1} = 8100 \text{ cfs} \quad \text{Height of surcharge}_1 = 6.4' \text{ (el 1214.4) see rating curve}$$

SURCHARGE VOLUME = TOTAL VOLUME - NORMAL POOL VOLUME (from elevation

$$STOR_1 = 4480 - 3251 = 1229 \text{ a-f} \quad \text{volume curve)}$$

$$STOR_1 = \frac{1229 \text{ a-f} \times 12 \text{ "/ft}}{3.44 \text{ mi}^2 \times 640 \text{ acre/mi}^2} = 6.6988''$$

$$Q_{P2} = Q_{P1} \left(1 - \frac{STOR_1}{19''}\right) = 8100 \left(1 - \frac{6.6988}{19}\right) = 5244 \text{ cfs}$$

$$\text{SURCHARGE HEIGHT}_2 = 5.18' \text{ (el 1213.18')}$$

$$STOR_2 = 4260 - 3251 = 1009 \text{ a-f}$$

$$STOR_2 = \frac{1009 \times 12}{3.44 \times 640} = 5.4996''$$

$$STOR_{Ave} = (5.4996 + 6.6988)/2 = 6.0992''$$

$$Q_{P3} = 8100 \left(1 - \frac{6.0992}{19}\right) = 5500 \text{ cfs}$$

$$\text{SURCHARGE HEIGHT}_3 = 5.3' \text{ (el 1213.3')}$$

$$STOR_3 = 4280 - 3251 = 1029 \text{ a-f}$$

$$STOR_3 = \frac{1029 \times 12}{3.44 \times 640} = 5.6086''$$

$$STOR_{Ave} = (5.6086 + 6.0992)/2 = 5.8539''$$

$$Q_{P4} = 8100 \left(1 - \frac{5.8539}{19}\right) = 5604 \text{ cfs}$$

$$\text{SURCHARGE HEIGHT}_4 = 5.33' \text{ (el 1213.33')}$$


$$STOR_4 = 4290 - 3251 = 1039 \text{ a-f}$$

$$STOR_4 = \frac{1039 \times 12}{3.44 \times 640} = 5.6632 \text{ cfs}$$


$$STOR_{Ave} = (5.6632 + 5.8539)/2 = 5.7586''$$

$$Q_{P5} = 8100 \left(1 - \frac{5.7586}{19}\right) = 5645 \text{ cfs}$$

$$\text{SURCHARGE HEIGHT}_5 = 5.34' \text{ (el 1213.34')}$$



ELEVATION - DISCHARGE
EAST LONG MOUND DAM
KMC 1/28/85



Job No. 91110 Sheet 9 of 44
 Project East Long Pond Dam Date 1/29/30
 Subject Hydraulics By AKC Ch'k. by

DAM CREST - ELEVATION 1211.5'

RIGHT EMBANKMENT

majority of 25 foot right embankment is a hill which will not be overtopped ($\approx 5'$ above left embankment). But small length of embankment before and after hill will obstruct flow - Length $\approx 20'$ - Elevation 1211.5

$$Q = C L H^{3/2}$$

$$C = 2.6 \text{ (conservative)}$$

$$Q = 2.6(20)(H^{3/2})$$

$$L = 20'$$

$$Q = 52 H^{3/2}$$

36" ϕ OUTLET PIPE - ASSUMED NON-EFFECTIVE IN FLOW COMPUTATIONS BECAUSE IT HAS A GATED OPENING. OPENING MECHANISM HAS BEEN REMOVED, AND IF REINSTALLED, WOULD BE IN MIDDLE OF SPILLWAY, MAKING USE DURING FLOOD IMPROBABLE

Job No. 91110 Sheet 8 of 44
 Project EAST LONG POINT DAM Date 11-1-17
 Subject HYDRAULICS / HYDROLOGY By AK Ch'k. by JS

EMERGENCY SPILLWAY - CREST ELEVATION 1208'

$$Q_{ES} = C_w L H^{3/2}$$

$$L = 80'$$

$$Q_{ES} = 3.1(80) H^{3/2}$$

$C_w = 3.1$ (conservative
value chosen due to field
conditions)

$$Q_{ES} = 248 H^{3/2}$$

DAM CREST - ELEVATION 1210'

Left Embankment near auxiliary spillway

$$Q = C_w L H^{3/2}$$

$$L = 95'$$

$$Q = 2.6(95) H^{3/2}$$

$C_w = 2.6$ (conservative
value chosen due to field
conditions)

$$Q = 247 H^{3/2}$$

DAM CREST - ELEVATION 1211.3'

Left Embankment near left abutment

$$Q = C_w L H^{3/2}$$

$$L = 80'$$

$$Q = 2.6(80) H^{3/2}$$

$C_w = 2.6$ (conservative
value chosen due to field
conditions)

$$Q = 208 H^{3/2}$$

Job No. 71110 Sheet 7 of 44
 Project EAST LEBAS FLOOD DAM Date 11-3-77
 Subject HYDRAULICS / HYDROLOGY By RC-Ch'k. by CS

STEP 1

CALCULATION OF SPILLWAY DESIGN FLOOD

CLASSIFICATION SIZE - INTERMEDIATE

HAZARD - HIGH

DAM SAFETY GUIDELINES RECOMMEND

PMF

PMF FOUND ON PMF CURVE ENVELOPE

Basin - MOUNTAINOUS

$$PMF = 2350 \text{ cfs} / \text{mi}^2$$

$$PMF = 2350 \frac{\text{cfs}}{\text{mi}^2} \times 3.44 \text{ mi}^2 = 8084 \text{ cfs} \approx 8100 \text{ cfs}$$

$$PMF = 8100 \text{ cfs}$$

$$1/2 \text{ PMF} = 4050 \text{ cfs}$$

OK
 Should be
 deleted.
 Duplicates previous
 page

STEP 2 (cont.)

CALCULATION OF SURCHARGE BY FULL PMF

AUXILIARY SPILLWAY - CREST ELEVATION 1208.8'

$$Q = C_w L H^{3/2}$$

$$Q_{ms} = 2.9 (12) H^{3/2}$$

$$Q_{ms} = 34.8 H^{3/2}$$

$$L = 12$$

$C_w = 2.9$ (conservative
 value chosen due to field -
 debris could obstruct
 weir)

Job No. 91118 Sheet 6 of 44
 Project NICHOLS POND DAM Date 11/2/79
 Subject HYDRAULICS / HYDROLOGY By RMC Ch'k. by

STEP 1 CLASSIFICATION OF SPILLWAY DESIGN FLOOD

CLASSIFICATION SIZE - INTERMEDIATE
 HAZARD - HIGH

DAM SAFETY GUIDELINES RECOMMEND
 FULL PMF

PFM NOT FOUND ON PMF CURVE ENVELOPE, DUE TO
 DRAINAGE AREA BEING LESS THAN 2 mi^2 . NEW ENGLAND
 DIVISION, CORPS OF ENGINEERS CONSULTED ON NOVEMBER 27, 1979.
 ENGINEER GARY JAMES RECOMMENDED USING SAME
 PMF / mi^2 AS LAST LONG POND DAM (1750' UPSTREAM) AND
 ADDING THE OUTPUT OF LAST LONG POND RESERVOIR TO
 GET THE INPUT PMF FOR NICHOLS POND RESERVOIR.

BASIN - MOUNTAINOUS

PMF FOR LAST LONG POND $2350 \text{ cfs} / \text{mi}^2$

DA FOR NICHOLS POND

$$\text{PMF} = 2350 \frac{\text{cfs}}{\text{mi}^2} \times 1.11 \text{ mi}^2 = 2608.5 \text{ cfs}$$

OUTFLOW FROM EAST LONG POND (caused by PMF)

$$\text{PMF} = 2608.5 + 5645 \text{ cfs} = 8253.5 \approx 8300 \text{ cfs}$$

calculations shown on pages 7-14

$$\text{PMF} = 8300 \text{ cfs}$$

OUTFLOW FROM East Long Pond (caused by $\frac{1}{2}$ PMF)

$$\frac{1}{2} \text{ PMF} = \frac{2608.5}{2} \text{ cfs} + 2450 \text{ cfs} = 3759.3 \text{ cfs} \approx 3800 \text{ cfs}$$

STEP 2 CALCULATION OF DISCHARGE BY PMF
DAM CREST ELEVATION 1130.5'

$$Q = C_w L H^{3/2}$$

$$Q = 2.00 (2.63) H^{3/2}$$

$$Q = 526 H^{3/2}$$

$$L = 200'$$

$C_w = 2.63$ from
 Kingard Brater

Page 5-46, Table E-3

BROAD CRESTED WEIR

Job No. 91118 Sheet 5 of 44
Project NICHOLS POND DAM Date 11-1-79
Subject HYDRAULICS / HYDROLOGY By LHC Ch'k. by JS

NICHOLS POND DAM - Located in Woodbury, VT

CLASSIFICATION: SIZE - INTERMEDIATE (Based on Storage)
HAZARD - HIGH (based upon location
of downstream homes)

BASIC DATA:


DRAINAGE AREA: INDEPENDANT 1.11 mi^2
TOTAL 4.55 mi^2
RESERVOIR: NORMAL POOL ELEVATION $1128'$ (USGS)
STORAGE 2590.4 a-f
MAXIMUM POOL ELEVATION $1130.5'$
STORAGE 2840.9 a-f
SURFACE AREA
 161.9 acres (NORMAL POOL)
 167 acres (MAXIMUM POOL)

DAM: EARTH FILL WITH CONCRETE UPSTREAM
WALL AND STONE MASONRY WALL DOWNSTREAM -
BOTH WALLS VERTICAL

MAXIMUM HEIGHT - $18'$
LENGTH - $200'$


SPILLWAY: PRIMARY - TRIANGULAR SHAPED
WEIR, TAPERS FROM $37'$ TO $7.5'$
EMERGENCY - NONE

OUTLET: $5' \times 2'$ SLUICeway
INVERT $1117' \pm$ AS PER
STATE OF VERMONT SURVEY



Job No. 91118 Sheet 3 of 44
 Project Nichols Pond Dam Date 12/12/79
 Subject Elevation - Volume Curve By Rmc Ch'k. by

ELEVATION	Area (acres)	$\frac{A_1 + A_2}{2}$ (acres)	HEIGHT (ft)	INCREMENTAL VOLUME (a - F)	TOTAL VOLUME (a - F)
1128	161.9	164.45	1.5	-	2590.4
1129.5	167.0	168.0	0.5	246.7	2837.1
1130	169.0	175.75	5.0	84.0	2921.1
1135	182.5	190.75	5.0	878.8	3799.9
1140	199.0			953.8	4753.7



Job No. 91118 Nichols Pond Sheet 1 of 44
 Project DAM INSPECTION Date 11/20/71
 Subject RESERVOIR DATA By AK Ch'k. by

NICHOLS POND DAM

NORMAL POOL SURFACE (ELEV. 1128') USGS

READING 1

0.27

READING 2

$0.52/2 = 0.26$

READING 3

$0.78/3 = 0.26$

AVERAGE = $0.78/3 = 0.26$

AREA = $0.26 \times 0.973 = 0.25 \text{ mi}^2 \times 640 = 161.9 \text{ acres}$

ADDITIONAL POOL TO BE OBTAINED VIA GRAPH ON PAGE 2,
 UTILIZING POOL AREA AT NEXT CONTOUR LEVEL (1140')

READING 1

0.32

READING 2

$0.64/2 = 0.32$

READING 3

$0.95/3 = 0.32$

AVERAGE = $0.95/3 = 0.32$

AREA = $0.973 \times 0.32 = 0.31 \text{ mi}^2 = 199 \text{ acres}$

NORMAL POOL STORAGE (1128') (vertical walls assumed)

HEIGHT TO SPILLWAY $\approx 16'$

$16' \times 161.9 \text{ acres} = 2590.4 \text{ acre-ft}$

SURCHARGE STORAGE (1129.5')

$1.5' \times 167 \text{ acres} = 250.5 \text{ acre-ft}$

MINIMUM POOL STORAGE

SUM OF SURCHARGE AND NORMAL STORAGE

$2590.4 + 250.5 = 2840.9 \text{ acre-ft}$

Job No. 91110 Sheet 41 of 44
 Project East Long Pond Date 4/10/80
 Subject Hydraulics By PMC Ch'k. by

$$STOR_4 = 3930 - 3251 = 679 \text{ a-f}$$

$$STOR_4 = \frac{679 \times 12}{3.44 \times 640} = 3.7009 "$$

$$STOR_{ave} = (3.7009 + 3.7827)/2 = 3.7418 "$$

$$Q_{P5} = 4050 \left(1 - \frac{3.7418}{9.5}\right) = 2455 \text{ cfs}$$

$$\text{surcharge height}_6 = 3.65' (\text{el } 1211.65)$$

$$\text{surcharge height}_6 = \text{surcharge height}_5 = 3.65' \approx 3.7' (\text{el } 1211.7')$$

values will not change, no further iterations necessary

CONCLUSIONS

- 1) Reservoir storage will reduce the Full PMF test inflow to an outflow of 5645 cfs (30% reduction). The $\frac{1}{2}$ PMF test inflow will be reduced, due to reservoir storage, to 2455 cfs (39% reduction)
- 2) The spillways can only pass 747 cfs before the dam is overtopped (13% of test outflow of 5645 cfs; 30% of test outflow of 2455 cfs)
- 3) The PMF will cause a dam overtopping of 3.3' (el. 1213.3'). $\frac{1}{2}$ PMF causes the dam to be overtopped by 1.7' (el 1211.7')

Job No. 91118 Sheet 15 of 44
 Project NICHOLS FOND DAM Date 11/28/79
 Subject HYDRAULICS / HYDROLOGY By RMC Ch'k. by CR

OUTLET ASSUMED NON EFFECTIVE IN FLOW COMPUTATIONS BECAUSE OUTLET IS GATED. GATE OPENING MECHANISM HAS BEEN REMOVED. ALSO, THE OPERATOR WOULD HAVE TO STAND IN THE MIDDLE OF THE SPILLWAY TO OPERATE THE GATES, MAKING ITS USE UNLIKELY DURING A FLOOD.


SPILLWAY

IRREGULAR SPILLWAY REQUIRES SPECIAL COMPUTATIONS TO DETERMINE IF INLET OR OUTLET CONTROLS FLOW. A RATING CURVE FOR THE SPILLWAY (shown as Page 6-516) INDICATES A CAPACITY OF 215 cfs AT DAM CREST (ELEVATION 1130.5') CONSEQUENTLY WHEN THE ENTIRE DAM IS OVERTOPPED (ELEV. 1130.5'), THE SPILLWAY WILL BECOME INSIGNIFICANT IN FLOW CALCULATIONS; THE WEIR-LIKE FLOW OVER THE DAM CREST WILL DOMINATE.

Job No. 91118 Sheet 16 of 44
 Project Nichols Pond Dam Date 11-28-71
 Subject Spillway Rating Curve By JZ Ch'k. by

1. Rating curve for downstream end

a. Sketch:



b. Find discharge for various depths at Critical Depth

Ref King & Brater p 8-8 (formulae 8-29)

$$Q = \sqrt{g} \cdot b \cdot D_c^{3/2}, (\sqrt{g} = 5.17; b = 7.25)$$


$$Q = 41.1 D_c^{3/2}$$

$$EGL = Z_0 + d_c + H_v, \text{ where } Z_0 = 1126.0; H_v = \frac{D_c}{2}$$

depth	$D_c^{3/2}$	Q	H_v	EGL	
0.5	0.35	15	0.25	1126.8	
1.0	1.0	41	0.5	1127.5	
2.0	2.83	116	1.0	1129.0	
3.0	5.2	214	1.5	1130.5	
4.0	8.0	329	2.0	1132.0	
6.0	14.7	603	3.0	1135.0	
8.0	22.6	928	4.0	1138.0	

Job No. 91116 Sheet 17 of 44
 Project Nichols Pond Dam Date 11-28-77
 Subject Spillway Rating Curves By J. Ch'k. by

2. Rating curve for upstream end of spillway
 a. sketch




Using same formula ($Q = \sqrt{g} L D_o^{3/2}$)
 we will combine b_1 and b_3 and investigate

$$b_4 = b_1 + b_3 = 28'$$

b. determine two rating curves and combine

$$b_1 = 28', Q = 158.8 D_o^{3/2}$$


d $z_o = 1128.0$	$D_o^{3/2}$	Q	H_v	EGL
0.5	.35	56	0.25	1128.6
1.0	1.0	159	0.5	1129.5
1.5	1.84	292	0.75	1130.3
2.0	2.82	449	1.0	1131.0
2.5	3.95	628	1.25	1131.8
$z_o = 1127.5$		$b_2 = 9', Q = 51.0 D_o^{3/2}$		
0.5	.35	18	0.25	1128.3
1.0	1.0	51	0.5	1129.0
1.5	1.84	94	0.75	1129.8
2.0	2.82	144	1.0	1130.5
2.5	3.95	202	1.25	1131.3
3.0	5.0	265	1.5	



Job No. 91118 Sheet 19 of 44
 Project NICHOLS POND DAM Date 11/28/79
 Subject HYDRAULICS / HYDROLOGY By PMC Ch'k. by JB

WATER SURFACE ELEVATION	PRIMARY SPILLWAY		DAM (el 1130.5) CRLST		TOTAL FLOW (cfs)
	HEAD (ft)	FLOW (cfs)	HEAD (ft)	FLOW (cfs)	
1127	0	-	0	-	0
1127.5	0	-	0	-	0
1128	0.5	13	0	0	13
1129	1.5	115	0	0	115
1130	2.5	183	0	0	183
1131	3.5	256	0.5	186	442
1132	4.5	330	1.5	966	1296
1132 *	-	-	2.5	2079	2079
1134 *	-	-	3.5	3444	3444
1135.5	3.0	218	0	0	218
1135 *	-	-	4.5	5021	5021
1136 *	-	-	5.5	6785	6785
1137 *	-	-	6.5	8717	8717
1138 *	-	-	7.5	10804	10804
1139 *	-	-	8.5	13035	13035

* Discharge over spillway not included above el. 1132
 because configuration of dam is assumed to control



Job No. 91118 Sheet 21 of 44
 Project Nichols Pond Dam Date 1/25/80
 Subject Hydraulics / Hydrology By MC Ch'k. by

STEP 3 EFFECT OF SURCHARGE STORAGE ON PMF

$$Q_{P_1} = 8300 \text{ cfs} \quad \text{HEIGHT OF SURCHARGE}_1 = 8.8' \quad (\text{el } 1136.8')$$

(see Rating Curve p. 40)

STOR₁ = SURCHARGE VOLUME = TOTAL VOLUME - NORMAL POOL VOLUME (see elevation volume curve p. 4)

$$\text{STOR}_1 = 4175 - 2590.4 = 1584.6 \text{ a-f}$$

$$\text{STOR}_1 = \frac{1584.6 \text{ a-f} \times 12 \text{ "/ft}}{4.55 \text{ mi}^2 \times 640 \text{ ac/mi}^2} = 6.5299''$$

$$Q_{P_2} = P_1 \left(1 - \frac{\text{STOR}_1}{19''}\right) = 8300 \left(1 - \frac{6.5299}{19}\right) = 5447 \text{ cfs}$$

$$\text{SURCHARGE HEIGHT}_2 = 7.3' \quad (\text{el } 1135.3')$$

$$\text{STOR}_2 = 3850 - 2590.4 = 1259.6 \text{ a-f}$$

$$\text{STOR}_2 = \frac{1259.6 \times 12}{4.55 \times 640} = 5.1907''$$

$$\text{STOR}_{\text{AVE}} = (5.1907 + 6.5299)/2 = 5.8603''$$

$$Q_{P_3} = 8300 \left(1 - \frac{5.8603}{19}\right) = 5740 \text{ cfs}$$

$$\text{SURCHARGE HEIGHT}_3 = 7.45' \quad (\text{el. } 1135.45')$$

$$\text{STOR}_3 = 3700 - 2590.4 = 1309.6 \text{ a-f}$$

$$\text{STOR}_3 = \frac{1309.6 \times 12}{4.55 \times 640} = 5.3967''$$

$$\text{STOR}_{\text{AVE}} = (5.3967 + 5.8603)/2 = 5.6285''$$

$$Q_{P_4} = 8300 \left(1 - \frac{5.6285}{19}\right) = 5841 \text{ cfs}$$

$$\text{SURCHARGE HEIGHT}_4 = 7.52' \quad (\text{el. } 1135.52')$$

$$\text{STOR}_4 = 3925 - 2590.4 = 1334.6 \text{ a-f}$$

$$\text{STOR}_4 = \frac{1334.6 \times 12}{4.55 \times 640} = 5.4997''$$

Job No. 91118 Sheet 22 of 44
 Project Nicolas Pond Dam Date 4/10/80
 Subject Hydrology By Rmc Ch'k. by

$$STOR_{ave} = (5.4777 + 5.6285) / 2 = 5.5641''$$

$$Q_{P5} = 2300 \left(1 - \frac{5.5641}{19} \right) = 5269 \text{ cfs}$$

$$\text{surchance height}_5 = 7.52' (\text{el. } 1135.52')$$

Surchance height₅ = surchance height₄ = 7.52' \approx 7.5'
 since will not change, no further iterations necessary

Since the dam is overtopped, 1/2 PMF must be routed nor determine spillway adequacy.

$$Q_{P1} = 3800 \text{ cfs} \quad \text{surchance height}_1 = 6.4' (\text{el. } 1134.4')$$

$$STOR_1 = \text{Surchance Volume} = \text{Total Volume} - \text{Normal pool volume}$$

$$STOR_1 = 3750 - 2590 = 1160 \text{ a-F}$$

$$STOR = \frac{1160 \text{ a-F} \times 12'' / \text{ft}}{4.55'' \times 640 \text{ ft}^2 / \text{acre}} = 4.7802''$$

$$Q_{P2} = 3800 \left(1 - \frac{4.7802}{7.5} \right) = 1288 \text{ cfs}$$

$$\text{surchance height}_2 = 4.8' (\text{el. } 1132.8')$$

$$STOR_2 = 3400 - 2590 = 810 \text{ a-F}$$

$$STOR_2 = \frac{810 \times 12}{4.55 \times 640} = 3.3377''$$

$$STOR_{ave} = (3.3377 + 4.7802) / 2 = 4.0591''$$

$$Q_{P3} = 3800 \left(1 - \frac{4.0591}{7.5} \right) = 2176 \text{ cfs}$$

$$\text{surchance height}_3 = 5.05' (\text{el. } 1133.05')$$

$$STOR_3 = 3425 - 2590 = 835 \text{ a-F}$$

$$STOR_3 = \frac{835 \times 12}{4.55 \times 640} = 3.4407''$$

$$STOR_{ave} = (3.4407 + 4.0591) / 2 = 3.7500''$$

$$Q_{P4} = 3800 \left(1 - \frac{3.7500}{7.5} \right) = 2200 \text{ cfs}$$

Job No. 71118 Sheet 22A of 44
 Project Wetlands Pond 1.2 m Date 4/10/80
 Subject Hydraulics / Hydrology By PM Ch'k. by

$$\text{surcharge height}_4 = 5.15' (\text{el. } 1133.15')$$

$$\text{STOR}_4 = 3450 - 2590 = 860 \text{ a-f}$$

$$\text{STOR}_4 = \frac{860 \times 12}{4.55 \times 640} = 3.5440''$$

$$\text{Slur out} = (3.5440 + 3.7500) / 2 = 3.6470''$$

$$Q_{P5} = 3200 \left(1 - \frac{3.6470}{9.5}\right) = 2341 \text{ cfs} \approx 5.2'$$

$$\text{surcharge height}_5 = 5.18' (\text{el. } 1133.18') \approx 1133.2'$$

$$\text{surcharge height}_5 = \text{surcharge height}_4 = 5.2' (\text{el. } 1133.2')$$

no further iterations necessary

CONCLUSIONS

1) Reservoir storage will reduce the full PMF test inflow to an outflow of 5869 cfs (29% reduction)
 the $1/2$ PMF test inflow will be reduced, due to reservoir storage, to 2341 cfs (38% reduction)

2) The spillway can only pass 215 cfs before the dam is overtopped. (4% of test discharge of 5869 cfs;
 7% of test discharge of 2341 cfs)

3) The PMF will cause a dam overtopping of 5.0' (el. 1135.5'). $1/2$ PMF causes the dam to be overtopped by 2.7' (el. 1133.2')

No. 71118 Sheet 23 of 44
 Project Michels Pond Dam Date 4/10/80
 Subject Hydraulics / Hydrology By RMC Ch'k. by

DOWNSTREAM DAMAGE ESTIMATE

Crops of Engineers recommends this procedure - Do breach analysis w/ water at top of dam (full spillway capacity used). Check to see if one or more homes will be affected) IF so, use this case. IF not, try analysis w/ water at top of spillway (negligible downstream flow). Using this method of analysis, a case will be found which will cause damage or loss of life (the object of the analysis)

Case 1. Water at top of dam (el. 1130.5)

$$Q_b = \frac{2}{27} W L \sqrt{g} Y_0^{3/2} = \frac{2}{27} (0.40) (175) \sqrt{32} 20^{3/2} = 10,500 \text{ cfs}$$

W = breach width

Y_0 = height of water above dam

initial downstream discharge = 218 cfs, stage = 1.8'

total flow after breach = 10,500 + 218 = 10,718 cfs, stage = 13.9'

FLOOD WAVE = Δ stage = 13.9 - 1.8' = 12.1'

a 12.1' wave will cause damage downstream of dam, hence

case 1 will be used

STEP 1 Reservoir Storage

@ el. 1130.5', $S = 2841 \text{ a-ft}$

STEP 2 Peak Failure outflow

Q_p = (from above calculations) 10500 cfs

STEP 3 STAGE - DISCHARGE ROUTING CURVE

No.
ect
ject

9/11/8


Sheet 24 of 44

Nichols Pond Dam

Date 1/28/80

Hydraulics / Hydrology

By RMC Ch'k. by




R- A/P

L=10,500'

$S = \frac{1123 - 933}{10000} = 0.0197$

$n = 0.03$ $n = 0.03$ $n = 0.03$

STAGE	AREA	CHANNEL	RIGHT	OVER	FLOW	LEFT	OVER	FLOW	TOTAL	TOTAL
(ft)	(sq ft)	WETTED PERIMETER	WETTED PERIMETER	WETTED PERIMETER	WETTED PERIMETER	WETTED PERIMETER	WETTED PERIMETER	WETTED PERIMETER	AREA	FLOW
4	24	28.35	10.2	10.2	2.5	10.2	10.2	2.5	84	595
6	123	28.25	10.2	10.2	2.5	10.2	10.2	2.5	148	1824
8	172	28.25	10.2	10.2	16.0	10.2	10.2	16.0	252	3229
10	216	28.25	10.2	10.2	47.1	10.2	10.2	47.1	396	5183
12	260	28.25	10.2	10.2	101.2	10.2	10.2	101.2	580	7801
14	304	28.25	10.2	10.2	183.3	10.2	10.2	183.3	804	11155
16	348	28.25	10.2	10.2	298.3	10.2	10.2	298.3	1068	15339



9/1/16

Sheet 26 of 44

MACVILLE POND DAM

Date 12/15/79

HYDRAULICS / HYDROLOGY

By RMC Ch'k. by

SPILLWAY CALCULATION OF SURCHARGE BY PMF
ELEVATION 925.0'

$$Q = C_w L H^{3/2}$$

$$L = 23 + 16 = 39'$$

$$Q = 3.1 (39) H^{3/2}$$

$C_w = 3.1$ (based upon field conditions)

$$Q = 120.9 H^{3/2}$$

DAM CREST ELEVATION 927.0'

$$Q = C_w L H^{3/2}$$

$$L = 80.5 - 39 = 41.5'$$

$$Q = 3.0 (41.5) H^{3/2}$$

$C_w = 3.0$ (based upon field conditions)

$$Q = 124.5 H^{3/2}$$

DIKE ELEVATION 929.3'

THE ROADWAY TO THE LEFT OF THE DAM HAS HAD FLOOD WATERS USE IT AS AN EMERGENCY SPILLWAY. IT WILL BE CONSIDERED AS A WEIR WITH A LENGTH OF 75', VERTICAL WALLS ARE ASSUMED TO STAY CONSERVATIVE.

$$Q = C_w L H^{3/2}$$

$$L = 75'$$

$$Q = 2.6 (75) (H^{3/2})$$

$C_w = 2.6$ (based upon field conditions)

$$Q = 195 H^{3/2}$$

OUTLET ASSUMED NON EFFECTIVE IN FLOW COMPUTATIONS.

WASTE GATE IS INOPERABLE AND THE PENSTOCK GATE OPENING MECHANISM IS LOCATED IN THE MIDDLE OF THE SPILLWAY, MAKING ITS USE UNLIKELY DURING A FLOOD.

AD-A156 255

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
NICHOLS POND DAM (VT. (U) CORPS OF ENGINEERS WALTHAM MA
NEW ENGLAND DIV APR 80


2/2

UNCLASSIFIED


F/G 13/13

NL

									END				



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A



91116

JB

12/11/79

29 of 44

Based on Available Information:
 USGS 15' Quadrangle, Plainfield, Vt.
 and DuBois and King Topographic Data

ELEVATION - STORAGE
 MACKVILLE DAM
 JJB 12/11/79

FEET

42.5

40.0

37.5

35.0

32.5

30.0

27.5

25.0

22.5

20.0

17.5

15.0

12.5

10.0

7.5

5.0

2.5

0.0

-2.5

-5.0

-7.5

-10.0

-12.5

-15.0

-17.5

-20.0

-22.5

-25.0

-27.5

-30.0

-32.5

-35.0

-37.5

-40.0

-42.5

-45.0

-47.5

-50.0

-52.5

-55.0

-57.5

-60.0

-62.5

-65.0

-67.5

-70.0

-72.5

-75.0

-77.5

-80.0

-82.5

-85.0

-87.5

-90.0

-92.5

-95.0

-97.5

-100.0

-102.5

-105.0

-107.5

-110.0

-112.5

-115.0

-117.5

-120.0

-122.5

-125.0

-127.5

-130.0

-132.5

-135.0

-137.5

-140.0

-142.5

-145.0

-147.5

-150.0

-152.5

-155.0

-157.5

-160.0

-162.5

-165.0

-167.5

-170.0

-172.5

-175.0

-177.5

-180.0

-182.5

-185.0

-187.5

-190.0

-192.5

-195.0

-197.5

-200.0

-202.5

-205.0

-207.5

-210.0

-212.5

-215.0

-217.5

-220.0

-222.5

-225.0

-227.5

-230.0

-232.5

-235.0

-237.5

-240.0

-242.5

-245.0

-247.5

-250.0

-252.5

-255.0

-257.5

-260.0

-262.5

-265.0

-267.5

-270.0

-272.5

-275.0

-277.5

-280.0

-282.5

-285.0

-287.5

-290.0

-292.5

-295.0

-297.5

-300.0

-302.5

-305.0

-307.5

-310.0

-312.5

-315.0

-317.5

-320.0

-322.5

-325.0

-327.5

-330.0

-332.5

-335.0

-337.5

-340.0

-342.5

-345.0

-347.5

-350.0

-352.5

-355.0

-357.5

-360.0

-362.5

-365.0

-367.5

-370.0

-372.5

-375.0

-377.5

-380.0

-382.5

-385.0

-387.5

-390.0

-392.5

-395.0

-397.5

-400.0

-402.5

-405.0

-407.5

-410.0

-412.5

-415.0

-417.5

-420.0

-422.5

-425.0

-427.5

-430.0

-432.5

-435.0

-437.5

-440.0

-442.5

-445.0

-447.5

-450.0

-452.5

-455.0

-457.5

-460.0

-462.5

-465.0

-467.5

-470.0

-472.5

-475.0

-477.5

-480.0

-482.5

-485.0

-487.5

-490.0

-492.5

-495.0

-497.5

-500.0

-502.5

-505.0

-507.5

-510.0

-512.5

-515.0

-517.5

-520.0

-522.5

-525.0

-527.5

-530.0

-532.5

-535.0

-537.5

-540.0

-542.5

-545.0

-547.5

-550.0

-552.5

-555.0

-557.5

-560.0

-562.5

-565.0

-567.5

-570.0

-572.5

-575.0

-577.5

-580.0

-582.5

-585.0

-587.5

-590.0

-592.5

-595.0

-597.5

-600.0

-602.5

-605.0

-607.5

-610.0

-612.5

-615.0

-617.5

-620.0

-622.5

-625.0

-627.5

-630.0

-632.5

-635.0

-637.5

-640.0

-642.5

-645.0

-647.5

-650.0

-652.5

-655.0

-657.5

-660.0

-662.5

-665.0

-667.5

-670.0

-672.5

-675.0

-677.5

-680.0

-682.5

-685.0

-687.5

-690.0

-692.5

-695.0

-697.5

-700.0

-702.5

-705.0

-707.5

-710.0

-712.5

-715.0

-717.5

-720.0

-722.5

-725.0

-727.5

-730.0

-732.5

-735.0


Job No. 91116 Sheet 30 of 44
 Project MACQUEVILLE POND DAM Date 12/1/79
 Subject HYDRAULICS / HYDROLOGY By PMC Ch'k. by OB

STEP 3

STAGE - DISCHARGE ROUTING CURVE

DOWNSTEAM XS APPROXIMATED FROM
 X SECTIONAL DATA SURVEYED BY DUBOIS AND KING PERSONNEL
 RELATING TO FLOOD INSURANCE STUDY FOR TOWN OF HARDWICK, VT

REACH 1



2 REACHES

Reach₁

$L = 1500'$
 $\Delta \text{elev} = 23'$

$$S = \frac{23}{1500} = 0.0153$$

Reach₂

$L = 500'$
 $\Delta \text{elev} = 67'$

$$S = \frac{67}{500} = 0.1340$$

Job No.
Project
Subject

9/11/6
Mackville Pond Dam
Hydraulics


Sheet 31 of 44
Date 1/29/80
By RMC Ch'k. by

MANNINGS EQUATION USED

$$Q = \frac{1.49}{n} A R^{2/3} S^{1/2} \quad R = A/P$$

STAGE (ft)	AREA (ft ²)	CHANNEL WETTED PERIMETER (ft)	FLOW (cfs)	RIGHT AREA (ft ²)	WETTED PERIMETER (ft)	OVERBANK FLOW (cfs)	LEFT AREA (ft ²)	WETTED PERIMETER (ft)	OVERBANK FLOW (cfs)	TOTAL AREA (ft ²)	TOTAL FLOW (cfs)
2	26	17.2	158	-	-	-	-	-	-	26	158
4	58	17.2	600	6	6.3	13	6	6.3	13	84	626
6	90	17.2	1248	24	12.6	85	24	12.6	85	138	1418
8	122	17.2	2072	54	19	249	54	19	249	230	2520
10	154	17.2	3054	96	25.3	537	96	25.3	537	346	4128
12	186	17.2	4125	150	31.6	966	150	31.6	966	486	6057
15	234	17.2	6038	253.5	41.1	1940	253.5	41.1	1940	741	9919
18	282	17.2	8231	384	50.6	3370	384	50.6	3370	1050	14972
21	330	17.2	10685	541.5	60.1	5323	541.5	60.1	5323	1413	21331

Area (sq ft)



Job No. 91116 Sheet 33 of 44
 Project Mackville Dam Date 1/29/80
 Subject Hydraulics By RMC Ch'k. by
REACH 2

Reach Length = 500'

$$\Delta \text{elev} = 887 - 820 = 67'$$


$$S = \frac{\Delta \text{elev}}{L} = \frac{67}{500} = 0.1340$$

B) Normal depth found via Manning's equation $Q = \frac{1.49}{n} A R^{2/3} S^{1/2}$

C) Critical depth from table B-4
 King and Brater p. B-53

* Refer to Hydraulic and Excavation tables
 US BR

X S Approximated from
 Topography



$n = 0.08$ rock channel, hvy. wood or


d	A *	R *	$R^{2/3}$	B	C
				Q_n	Q_c
STAGE	AREA	HYDRAULIC		NORMAL	CRITICAL
(ft)	(ft ²)	RADIUS		FLOW	FLOW
				(cfs)	(cfs)
2	44	1.71	1.43	429	338
4	96	3.07	2.11	1377	1008
6	156	4.22	2.61	2770	1953
8	224	5.25	3.02	4603	3168
10	300	6.21	3.34	6809	4658
12	384	7.12	3.65	9538	6435
14	476	7.99	3.94	12,758	8500
16	576	8.83	4.21	16,492	10875

Assume critical depth at throat

40 1020

K02 H&M IN THE UNITED STATES OF AMERICA
HEUFFEL & ESSER CO. MADE IN U.S.A.

Area (ft²)



Job No. 91116 Sheet 35 of 44
 Project Mackville Pond Dam Date 1/29/80
 Subject Hydraulics By PMC Ch'k. by

AT CONFLUENCE W/COOPER BROOK, FLOOD WAVE WILL MEET A LARGE OPEN AREA, which acts as a reservoir. ELEVATION-STORAGE CURVE WILL BE DERIVED, EFFECTS ON FLOOD WAVE WILL BE DETERMINED USING OUTLET CHANNEL AS A CONTROL.

MAP SCALE 1" = 400'

CONVERSION


FACTOR
FOR

PLANIMETER

$$1" = (400')^2 \times \frac{1 \text{ acre}}{43560 \text{ ft}^2} = 3.673 \text{ acre}$$

$$1" = 3.673 \text{ acre}$$

ELEVATION (ft)	PLANIMETER READINGS		AVERAGE AREA (acre)	AVERAGE AREA (acre)	SLICE HEIGHT (ft)	INCREMENTAL VOLUME (a-ft)	TOTAL VOLUME a-f
	#1 (in ²)	#2 (in ²)	#3 (in ²)				
							0
313	-	-	-	0			
					7.88	3	23.64
316	4.27	4.29	4.31	4.29	15.76		
					23.14	4	92.56
320	8.32	8.30	8.30	8.31	30.51		116.20
					38.09	4	152.36
324	12.50	12.40	12.40	12.43	45.67		268.50



Job No. 91116 Sheet 37 of 44
 Project Mackville Dam Date 1/29/90
 Subject Hydraulics By RMC Ch'k. by
REACH 3

REACH CHARACTERISTICS

$$L = 2600'$$

$$\Delta elev = 814 - 806 = 8'$$


$$S = \Delta elev / L = 8 / 2600 = 0.0031$$

MANNINGS EQUATION USED

$$Q = \frac{1.49}{n} A R^{2/3} S^{1/2}$$


$$R = A/P$$

X S Approximated from
 topography
 channel itself neglected due to
 extreme overbank widths



$n = 0.05$ Rock channel,
 Brush overbanks

STAGE (ft)	AREA (ft ²)	WETTED PERIMETER (ft)	R	$R^{2/3}$	Q (cfs)
2	410	210.8	1.945	1.559	1061
4	840	221.5	3.792	2.433	3391
6	1290	232.3	5.553	3.138	6716
8	1750	243.1	7.199	3.731	10,833
10	2250	253.9	8.862	4.285	15,997
12	2760	264.6	10.430	4.777	21,676



Job No. 91118 Sheet 39 of 44
 Project Nichols Pond Dam Date 1/29/30
 Subject Channel Routing By PM Ch'k. by

STEP 4

$$Q_{P_1} = 10,250 \text{ cfs}$$

ENTER NICHOLS POND REACH 1 (refer p. 23-25)

$$\text{Stage} = 13.7'$$

$$\text{area} = 775 \text{ ft}^2$$

$$V_1 = \frac{10,500' \times 775 \text{ ft}^2}{43560 \text{ ft}^2/\text{acre}} = 186.8 \text{ a-f} < \frac{2841}{2} \text{ a-f} \therefore L_1$$

$$L_1 = 10,500'$$

$$Q_{P_{L_{100}}} = 10,250 \left(1 - \frac{186.8}{2841}\right) = 9576 \text{ cfs}$$

$$\text{Stage} = 13.3'$$

$$\text{area} = 735 \text{ ft}^2$$

$$V_2 = \frac{735 \text{ ft}^2 \times 10,500'}{43560} = 177.2 \text{ a-f}$$

$$V_{ave} = (177.2 + 186.8)/2 = 182.0 \text{ a-f}$$

$$Q_{P_2} = 10250 \left(1 - \frac{182}{2841}\right) = 9593 \text{ cfs} \approx 9600 \text{ cfs}$$

$$\text{OUTFLOW} = 9600 \text{ cfs}$$

$$\text{Stage} = 13.3'$$

(Refer p. 26-29)

ENTER MACKVILLE POND, assumed filled to elevation 927.0'

INVESTIGATE 'SURCHARGE STORAGE' EFFECTS ON FLOW

$$Q_{P_1} = 9600 \text{ cfs}$$

$$\text{HEIGHT}_1 = 10.2' (21935.2) \text{ (refer to Mackville Rating Curve, page 28)}$$

$$V_1 = \text{SURCHARGE STORAGE} = 377.5 - 182 = 195.5 \text{ a-f}$$

$$Q_{P_2} = Q_{P_1} \left(1 - \frac{V_1}{2841}\right) = 9600 \left(1 - \frac{195.5}{2841}\right) = 8739 \text{ cfs}$$

$$\text{SURCHARGE HEIGHT}_2 = 7.8' \text{ (elev. 934.8')}$$

$$V_2 = 370 - 182 = 188 \text{ a-f}$$

Job No. 91118 Sheet 40 of 44
 Project Nichols Pond Dam Date 1/29/80
 Subject Channel Routing By Rm Ch'k. by

$$Q_{p2} = 9600 \left(1 - \frac{188}{2841}\right) = 8965 \text{ cfs}$$

$$\text{SURCHARGE HEIGHT}_3 = 9.8' \text{ (el 934.8')}$$

$\text{SURCHARGE HEIGHT}_3 = \text{SURCHARGE HEIGHT}_2 = 9.8'$, NO FURTHER
 ITERATIONS NECESSARY (NOTE: FLOW DIVIDED IMMEDIATELY DSO OF DAM)

ENTER REACH 1 - MACKVILLE DAM (Refer P. 30-32)

$$Q_{p1} = 8965 \text{ cfs} \quad \text{stage} = 14.4' \quad \text{area} = 680 \text{ ft}^2$$

$$V_1 = \frac{680 \text{ ft}^2 \times 1500'}{43560 \text{ ft}^2/\text{acre}} = 23.4 \text{ ft} < \frac{2841 \text{ ft}^2}{2}$$

Length, OK

$$L_1 = 1500'$$

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_1}{2841}\right) = 8965 \left(1 - \frac{23.4}{2841}\right) = 8891 \text{ cfs}$$

$$\text{stage} = 14.4' \quad \text{area} = 680 \text{ ft}^2$$

$$V_2 = \frac{680 \times 1500}{43560} = 23.40 \text{ ft} = V_{ave}$$

$$Q_{p2} = 8965 \left(1 - \frac{23.4}{2841}\right) = 8891 \text{ cfs}$$

$$\text{OUTFLOW} = 8891 \text{ cfs} \quad \text{stage} = 14.4'$$

ENTER REACH 2 - MACKVILLE DAM (Refer P. 33-34)

$$Q_{p1} = 8891 \text{ cfs} \quad \text{stage} = 14.4' \quad \text{area} = 495 \text{ ft}^2$$

NOTE: FLOW IS CRITICAL AT THROAT

$$V_1 = \frac{500' \times 495 \text{ ft}^2}{43560} = 5.7 \text{ ft} < \frac{2841 \text{ ft}^2}{2}$$

Length, OK

$$L_2 = 500'$$

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_1}{2841}\right) = 8891 \left(1 - \frac{5.7}{2841}\right) = 8873 \text{ cfs}$$

Job No. 91118 Sheet 4 of 44
 Project Nichols Pond Dam Date 1/29/80
 Subject Channel Routing By RMC Ch'k. by

(Normal depth) stage = 11.6' area = 370 ft²

$$V_2 = \frac{370 \text{ ft}^2 \times 500'}{43560 \text{ ft}^2/\text{acre}} = 4.3 \text{ a-f}$$

$$V_{ave} = (5.7 + 4.3) / 2 = 5 \text{ a-f}$$

$$Q_{P2} = 8871 \left(1 - \frac{5.0}{2841}\right) = 8875 \text{ cfs}$$

$$\text{stage} = 11.6' \quad \text{OUTFLOW} = 8875 \text{ cfs}$$

ENTER CONFLUENCE NICHOLS - COOPERS BROOK (refer 35-36)

- 1) $Q_{P1} = 8875 \text{ cfs}$
- 2) Rating curve for exit channel controls, from stage-discharge curve $d_1 = 7.1'$
- 3) Elevation of valley floor = 814.0 (at exit channel)
- 4) Elevation of water surface = 814.0 + 7.1 = 821.1'
- 5) Enter volume-elevation curve, $V_{\text{storage}} = 152 \text{ a-f} < \frac{2841 \text{ a-f}}{2} \therefore \text{OK}$

$$Q_{P2(\text{revised})} = Q_{P1} \left(1 - \frac{V}{2841}\right) = 8875 \left(1 - \frac{152}{2841}\right) = 8400 \text{ cfs}$$

$$d_2 = 6.9' \text{ (at } 820.9) \quad V_2 = 144.5 \text{ a-f}$$

$$V_{ave} = (152 + 144.5) / 2 = 148.25 \text{ a-f}$$

$$Q_{P2} = 8875 \left(1 - \frac{148.25}{2841}\right) = 8412 \text{ cfs}$$

$$d_3 = 6.9' \text{ (at } 820.9) \quad V_2 = 144.5 \text{ a-f}$$

$$V_{ave} = (148.25 + 144.5) / 2 = 146.38 \text{ a-f}$$

Job No. 91118 Sheet 42 of 44
 Project Nichols Pond Dam Date 1/30/80
 Subject Channel Routing By RMC Ch'k. by

$$Q_{P3} = 8875 \left(1 - \frac{146.38}{2841}\right) = 8418 \text{ cfs}$$

$$d_4 = 6.9' \text{ (el. 820.9')}$$

NO FURTHER ITERATIONS, VALUES WILL NOT CHANGE SIGNIFICANTLY

$$\text{OUTFLOW} = 8418 \text{ cfs} \quad \text{stage (@ exit)} = 6.9'$$

ENTER MACKVILLE DAM REACH 3 (Refer p. 37-38)

$$\text{INFLOW} = 8418 \text{ cfs} \quad \text{stage} = 6.9' \quad \text{area} = 1480 \text{ ft}^2$$

$$V_1 = \frac{2600' \times 1480 \text{ ft}^2}{43560 \text{ ft}^2/\text{acre}} = 88.3 \text{ a-f} < \frac{2841}{2} \text{ a-f}$$

$$L_3 = 2600'$$

Reach length ok

$$Q_{P2} = 8418 \left(1 - \frac{88.3}{2841}\right) = 8156 \text{ cfs}$$

$$\text{stage} = 6.8' \quad \text{area} = 1460 \text{ ft}^2$$

$$V_2 = \frac{2600' \times 1460 \text{ ft}^2}{43560 \text{ ft}^2/\text{acre}} = 87.1 \text{ a-f}$$

$$V_{\text{ave}} = (87.1 + 88.3)/2 = 87.7 \text{ a-f}$$

$$Q_{P2} = 8418 \left(1 - \frac{87.7}{2841}\right) = 8158 \text{ cfs}$$

$$\text{OUTFLOW} = 8158 \text{ cfs} \quad \text{stage} = 6.8'$$

ENTER OUTSKIRTS VILLAGE OF HARDWICK


Job No. 91118 Sheet 43 of 44
 Project Nichols Pond Dam Date 1/30/80
 Subject Hydraulics By RMCh'k. by

FLOOD ROUTING SUMMARY

<u>REACH</u>	<u>DISCHARGE</u>	<u>STA. EL</u>	<u>FLOOD WAVE</u>
AT NICHOLS POND DAM	10,250 cfs	13.7'	11.9'
AT CONFLUENCE WITH MACKVILLE POND (10,500' DOWNSTREAM OF NICHOLS DAM)	9600 cfs	13.3'	11.4'
AT MACKVILLE DAM (13,000' DOWNSTREAM OF NICHOLS DAM) REDUCTION BY SURCHARGE STORAGE	8965 cfs		
			assume negligible discharge from Mackville pond
DOWNSTREAM OF MACKVILLE DAM	8965 cfs	14.4'	14.4'
1500' DOWNSTREAM OF MACKVILLE DAM (14500' DS OF NICHOLS DAM)	8891 cfs	14.4'	14.4'
2000' DOWNSTREAM OF MACKVILLE DAM (15,000' DS OF NICHOLS DAM)	8875 cfs	11.6'	11.6'
3800' DOWNSTREAM OF MACKVILLE DAM (16800' DS OF NICHOLS DAM) AFTER LARGE OPEN AREA	8418 cfs	6.7'	6.9'
6400' DOWNSTREAM OF MACKVILLE DAM (19,400' DOWNSTREAM OF NICHOLS DAM) OUTSKIRTS OF VILLAGE OF HARDWICK	8158 cfs	6.8'	6.8'

Job No. 91118
 Project NICHOLS POND DAM
 Subject RESERVOIR CAPACITY DATA


Sheet 44 of 44
 Date 11/29/77
 By RMC Ch'k. by



NOT TO SCALE

TEST INFLOW = 8300 cfs

SPILLWAY CAPACITY NICHOLS POND DAM						
CONDITION AT DAM	WATER SURFACE ELEVATION	TOTAL DISCHARGE (cfs)	PRIMARY SPILLWAY CONTRIBUTION		EMERGENCY SPILLWAY CONTRIBUTION	
			DISCHARGE (cfs)	% OF TOTAL DISCHARGE	DISCHARGE (cfs)	% OF TOTAL DISCHARGE
ENTIRE CREST OF DAM OVERTOPPED	1135.5	5667	600	10%		
RESERVOIR FILLED TO DAM CREST	1130.5	218	218	100%		
WATER AT SPILLWAY INVERT	1128	0	0	0%		



DuBois & King Inc.

engineering and environmental services
RANDOLPH VERMONT CONCORD NEW HAMPSHIRE


NATIONAL DAM INSPECTION PROGRAM

NICHOLS POND DAM

DRAINAGE AREA

USGS QUAD - PLAINFIELD, VERMONT

DRAWN BY	JAS	DATE	12/79
CHECKED BY	RMC	PROJ. NO.	91118
PROJ. ENG.		DRAW. NO.	
SCALE: 1"=62500			



POSSIBLE FLOOD
DAMAGE AREA DUE TO
DAM FAILURE

NICHOLS POND
DAM

**DuBois
& King**

engineering and environmental services
RANDOLPH VERMONT / CONCORD NEW HAMPSHIRE

NATIONAL DAM INSPECTION PROGRAM

NICHOLS POND DAM

POSSIBLE FLOOD DAMAGE AREA

USGS QUAD. - PLAINFIELD, VERMONT

DRAWN BY JAS	DATE 12/79
CHECKED BY KMC	PROJ. NO. 91118
PROJ. ENG. CB	DRAW. NO.
SCALE: 1" = 62500	

APPENDIX E
INFORMATION AS CONTAINED IN THE
NATIONAL INVENTORY OF DAMS

END

FILMED

8-85

DTIC